

ADDENDUM NO. 1

RE:	Indiana University Bloomington BL439 McNutt Central Renovation of Existing Apartment
OWNER:	The Trustees of Indiana University Bloomington, Indiana
PROJECT No.:	20241429
ARCH. PROJECT No.:	25-03
DATE:	April 29, 2025
ISSUED BY:	Springpoint Architects, p.c. 522 West 2 nd Street Bloomington, IN 47403
TO:	Bidders

This Addendum modifies the Bidding Documents dated April 16, 2025, and will become part of the Contract Documents. Acknowledge receipt of this Addendum on Bid Form. Failure to do so may subject the Bidder to disqualification.

GENERAL CLARIFICATIONS:

- 1. Reference attached Pre-Bid Meeting Agenda dated April 23, 2025.
- 2. Reference attached Pre-Bid Sign-In Sheet dated April 24, 2025.
- 3. Site Access has been modified reference Details 'C' and 'D' on revised COVER sheet, see attached.
- 4. HVAC: The owner's pre-purchased air handling unit has a lead time of 14 weeks. The unit will be released no later than May 9, 2025. The intent is that all other HVAC work in the surrounding apartments can be completed while waiting for the unit.
- 5. The existing walls to be removed on are presumed to be non-load bearing CMU, unless otherwise noted.
- 6. The existing roof and ceiling structure are concrete waffle slab construction on concrete beam and column super-structure.

CHANGES TO BIDDING REQUIREMENTS:

- 1. The date of Substantial Completion has been changed to November 15, 2025.
- 2. Replace BID FORM with attached. Bidders must use the bid form contained within this addendum.



CHANGES TO SPECIFICATIONS:

1. Add section 232923 Variable Frequency Controllers

CHANGES TO DRAWINGS:

- Add Siemens temperature controls drawings. Owner is providing parts and programming as part of the pre-purchase program. The Controls Installation Contractor shall install all owner devices, and provide and install all raceway, wiring, etc. The Controls Installation Contractor shall be a sub to the HVAC contractor, and all of these costs shall be included with the unified bid.
- 2. Sheet H203 3RD FLOOR HVAC PLAN
 - a. Added location of building pressure sensor.
- 3. Sheet $E302A 2^{ND}$ FLOOR POWER AND SYSTEMS PLAN
 - a. Added keynote #E15.
- 4. Sheet E303 3RD FLOOR POWER AND SYSTEMS PLAN
 - a. Added data drop for temperature control panel in Mech C397. Added keynote #E16.
 - b. See added General Note "I" for revised scope for data cabling.

LIST OF ATTACHMENTS:

- 1. Pre-Bid Meeting Agenda dated April 23, 2025
- 2. Pre-Bid Sign-In Sheet dated April 23, 2025
- 3. BID FORM
- 4. Specification Section "232923 Variable Frequency Controllers"
- 5. Siemens Temperature Control Drawings
- 6. Drawing Sheet "COVER"
- 7. Drawing Sheet "H203 3RD FLOOR HVAC PLAN"
- 8. Drawing Sheet "E302A 2ND FLOOR POWER AND SYSTEMS PLAN"
- 9. Drawing Sheet "E303 3rd FLOOR POWER AND SYSTMES PLAN"



Indiana University Bloomington BL439 McNutt Central Renovation of Existing Apartments #20241429 PRE-BID Meeting Agenda April 23, 2025

- I. Introductions
 - A. Bob Richardson, IU Capital Planning & Facilities Team Lead
 - B. Gary Chambers, IU Construction Project Manager
 - C. Larry Isom,
 - D. Dawn Gray, Springpoint Architect
 - E. Bill Stacey, CMTA Engineers
- II. Sign-in Sheet
- III. Bids Due: Wednesday, May 7, 2025, 2pm.
- IV. Project Timeframe (reference Summary of Work Section 01100):
 - A. Construction Start May 21, 2025
 - B. Substantial completion September 15, 2025.
 - C. Questions during bidding should be addressed to Dawn Gray, dawn@springpointarchitects.com, email preferred. Monday May 5th Final Addendum to be issued. Questions in by noon, May 2nd.
- V. Bidding Requirements, reference Instruction to Bidders in the project specification manual:
 - A. 5% bid security
 - B. Contractors written drug testing program
 - C. Contractors Minority and Women's Business Enterprise Participation Plan
- VI. Project Requirements
 - A. General Conditions & IU Standard supplementary conditions and modifications in front end. Refer to Capital Planning and Facilities Divisions 00 and 01.
 - B. Payment and Performance Bond
- VII. Documents Available thru the IU Plan hosted by Eastern Engineering and sets are available to view at the Springpoint Architects office
- VIII. Project Identification: Project includes construction of Apartment Renovations at the Third Floor of BL439 McNutt Central, 1101 Fee Lane at Indiana University's Bloomington Campus



as shown on the Construction Documents prepared by Springpoint Architects, P.C., and their consultants, dated April 16, 2025.

- A. Project will be constructed by a General Contractor as a single prime construction contract.
- B. Contractor Access to Site:
 - 1. Access to the project site will be limited and final arrangements will be coordinated with owner prior to construction beginning:
 - a. Existing materials that are to be removed and new materials to be installed must go through the third floor windows as shown.
 - Hours from removing and stocking material are limited to between 1:30 4:00 pm.
 - c. Pedestrian walkways and ADA ramp must be restricted and supervised by the contractor during the removal and stocking of materials.
 - d. Building elevator use will be limited to the transport of the following:
 - i. Air Handler Unit
 - ii. One-piece bathtub and shower enclosures
 - iii. Other items will be at the discretion of the owner
 - e. Final locations of site access elements must be coordinated and verified with owner before beginning construction
 - f. Contractor is responsible for projecting basement with plywood or other approved material prior to dumpster installation.
 - g. Construction fencing per IU's standards is required.
 - 2. Site Access plan and details will be part of Addendum No.1
 - 3. The contractor is responsible for construction barriers and additional dust management required to complete the project.
 - 4. The contractor is responsible for protecting all finishes to remain, including walls, floors, elevators, etc. in the project area and routes, interior and exterior, to the project area.
- C. Project Description
- 1. The work includes the construction of restroom upgrades:
 - a. The work includes the construction of two apartments on the 3rd floor. The project consists of the demolition of interior walls, ceilings, and flooring with new construction of cmu walls, metal stud walls, bulkheads, doors and frames. The finishes include acoustical tile ceilings, resilient tile, and sheet flooring, wall paint, and wood cabinetry with plastic laminate countertops, and solid surface countertops with integral sinks. Apartments are to be accessible with ADA compliant fixtures and accessories.



- b. The HVAC work includes the demolition of existing fin-tube heating system and installation of a new air handler unit, VAV boxes, ductwork, and controls to serve the third floor.
- c. Plumbing work includes the demolition of existing plumbing fixtures and associated lines and fitting. The new plumbing works includes ADA compliant plumbing fixtures and piping including kitchen sink, lavatories, toilets (wall hung), bath tub/shower and shower unit.
- d. The electrical work includes demolition of power, and lighting. The new work includes new power, and LED light fixtures.
- e. The work includes revisions to sprinkler piping.



INDIANA UNIVERISTY - BLOOMINGTON

BL439 McNutt Central – Renovation of Existing Apartments

PAGE 1

Project No. 20241429

SIGN-IN SHEET

April 23, 2025

	bobrichs in ear	212 · 805-1692	, representation a ded
	cubitlew & c-cat.com)/(I-CAT
	BLOBENSON @ BUELDENS ASSOCIATES. COM	6522 - 526 218	BEN ROBINSPU
1	Mhalcombodharrell-fish.com	317-517-5541	Mallory Halcomb - HFI
- Con	tong a tox Construction Con	812-327-0149	Town Fox - Fox Coust
	bothers @ werdicbros. com	(d12)-345-830g	Brooks De Wees / wedale
	al; anwitherer of MENT. Com	273-585-5832	AL: RASHAP NWP DEVELOPMENT
i a ler	Hoados Q Conner ail Seria Con	4116-655.213	Tyle Dogles LSD
	randy costerster. can	317-506-2110 Cell	RALDI COUCH/TERSTEP 317-506-2110 Cell
	restinating Octions. net	(812)232-3327 (office)	Trace Harnuff/CDI-
	EMAIL ADDRESS	TELEPHONE	NAME

522 WEST 2ND STREET | BLOOMINGTON IN 47403 | 812.318.2930 | WWW.SPRINGPOINTARCHITECTS.COM

BID FORM

for

BL439 McNutt Central **Renovation of Existing Apartments** Indiana University Bloomington Bloomington, Indiana IU 20241429

TO: The Trustees of Indiana University Bloomington, Indiana

**Submit bid online via www.iuplanroom.com **

FROM:

Bidder's Name			
Address			
City, State, Zip Code			
Phone Number		FAX Number	
CONTACTS:			
Bid / Contract Information:	Name:		
Phone:		E-mail:	
Proposed Project Manager:	Name:		
Phone:		E-mail:	

Indicate if your firm is a certified minority-, women-, or veteran-owned business _____ Yes ____ No If "Yes", please attach a copy of certification

FOR: Unified Bid to include General, Mechanical, and Electrical Construction Work

Bidders:

LUMP SUM BASE BID

The undersigned Bidder, with a complete understanding of existing conditions at the Project Site and a complete understanding of the Bidding Documents, including any Addenda acknowledged hereinafter, for BL439 McNutt Central – Renovation of Existing Apartments on the Indiana University Bloomington campus, as prepared by Springpoint Architects, pc, hereby proposes to complete the project, in full and complete accordance with the requirements of the Bidding documents, for the LUMP SUM BASE BID PRICE of:

(written amount)

_Dollars \$_____(numerals)

MAJOR SUBCONTRACTORS

Subcontractors and other persons and organizations proposed by the Bidder and accepted by the Owner and the Owner's Representative must be used on the work for which they were proposed and accepted and shall not be changed except with the written approval of the Owner and the Owner's Representative.

If requested, the supplemental Subcontractors and Products List will be submitted by email to the Owner, <u>bidtab@iu.edu</u>, and Springpoint Architects, <u>dawn@springpointarchitects.com</u> within 48 hours of the bid opening. The understanding of the Owner and the design team is that these same Major Subcontractors will be the same subcontractors listed below.

The Contractor proposes to utilize the following primary subcontractors for the work indicated.

<u>List one major subcontractor per trade</u>. Any deviation could result in the Owner removing the bid from consideration.

Indicate which are certified by the State of Indiana as an MBE, WBE, or VBE company by circling the M/W/VBE after the name.

MECHANICAL:	_ M/W/VBE
ELECTRICAL:	M/W/VBE
PLUMBING:	M/W/VBE

TAX EXEMPTIONS

The undersigned Bidder has informed himself and all his prospective sub-contractors and suppliers of the tax exempt status of the Owner, as set forth in the General Conditions, and therefore, has <u>not</u> included these taxes in his Lump Sum Base Bid price.

SUBSTITUTIONS

The undersigned Bidder has based his bid upon the materials, products, articles, equipment, brands, manufacturers and processes described in the Bidding Documents or upon approved equivalents. Proof of equivalency of substitutions is the responsibility of the Bidder, but the Architect/Engineer shall be the sole judge of equivalency. Proposed equivalent substitutions shall be equal in all respects to the requirements of the Bidding Documents, including but not limited to the design, quality, physical size, performance characteristics, strength, previous history of use, and to the method of installation, attachment, or connection to related or adjoining work. Determination of equivalency of proposed substitutions shall be by the Architect/Engineer, before the bid opening date, as described in paragraph entitled "Substitutions" in the Instructions to Bidders.

COMPLETION DATE

The Undersigned Bidder agrees to coordinate and expedite his work, and shall take into consideration

BL439 McNutt Central Renovation of Existing Apartments any lead time and schedule parameters, with all contractors and that this Work will be completed no later than November 15, 2025.

ASSIGNMENT OF COORDINATION

The undersigned Bidder agrees, to the assignment of Mechanical and Electrical work to the successful General Contractor for the responsibility of complete coordination of the work as stated in the Instructions to Bidders.

PERFORMANCE AND PAYMENT BOND

The undersigned Bidder agrees, if awarded the Contract, to deliver to the Owner a satisfactory Performance Bond, in the full amount (100%) of the total Contract price, not later than the date of execution of the contract. The cost of the Bond shall be included in the Lump Sum Base Bid contained in this Proposal.

SUPPLEMENTAL AND REQUIRED DOCUMENTS

Bid Security; State Form 96 (Revised 2013); Written Drug Testing Program, which must be in full compliance with IC 4-13-18; a completed Minority, Women's and Veteran's Business Enterprise Participation Plan; Contractor Asbestos Certification; Asbestos Protocol for Contractors.

ADDENDA

The following Addenda have been received by the undersigned Bidder; and all costs resulting from these Addenda have been included in the preparation of this Bid Form:

Addendum No.	Dated
Addendum No.	Dated
Addendum No.	Dated

SIGNATURES

1. When a Bidder is an Individual:

Witness	Bidder
Date:	Address:
When a Bidder is a Partnership:	Name of Partnership
Date:	Address:
Partner	Partner
	Page 3 of 4

When Bidder is a Corporation: 3. Name of Corporation Address: Date: _____ By: ______ President

Attest:_____ Secretary

CORPORATE SEAL

END

**Submit bid online via www.iuplanroom.com

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes solid-state, IGBT, VFCs for speed control of three-phase, squirrel-cage induction motors.

1.3 DEFINITIONS

- A. BMS: Building management system.
- B. IGBT: Integrated gate bipolar transistor.
- C. LAN: Local area network.
- D. PID: Control action, proportional plus integral plus derivative.
- E. PWM: Pulse-width modulated.
- F. VFC: Variable frequency controller.

1.4 SUBMITTALS

- A. Product Data: For each type of VFC. Include dimensions, mounting arrangements, location for conduit entries, shipping and operating weights, and manufacturer's technical data on features, performance, electrical ratings, characteristics, and finishes.
- B. Shop Drawings: For each VFC.
 - 1. Include dimensioned plans, elevations, sections, and details, including required clearances and service space around equipment. Show tabulations of installed devices, equipment features, and ratings. Include the following:
 - a. Each installed unit's type and details.
 - b. Nameplate legends.
 - c. Short-circuit current rating of integrated unit.
 - d. Listed and labeled for series rating of overcurrent protective devices in combination controllers by an NRTL acceptable to authorities having jurisdiction.

- e. Features, characteristics, ratings, and factory settings of each motor-control center unit.
- 2. Wiring Diagrams: Power, signal, and control wiring for VFCs. Provide schematic wiring diagram for each type of VFC.
- C. Coordination Drawings: Floor plans, drawn to scale, showing dimensioned layout, required working clearances, and required area above and around VFCs where pipe and ducts are prohibited. Show VFC layout and relationships between electrical components and adjacent structural and mechanical elements. Show support locations, type of support, and weight on each support. Indicate field measurements.
- D. Field quality-control test reports.
- E. Operation and Maintenance Data: For VFCs, all installed devices, and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 1 Section "Operation and Maintenance Data," include the following:
 - 1. Routine maintenance requirements for VFCs and all installed components.
 - 2. Manufacturer's written instructions for testing and adjusting overcurrent protective devices.
- F. Load-Current and List of Settings of Adjustable Overload Relays: Compile after motors have been installed and arrange to demonstrate that dip switch settings for motor running overload protection suit actual motor to be protected.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer. Maintain, within 100 miles of Project site, a service center capable of providing training, parts, and emergency maintenance and repairs.
- B. Source Limitations: Obtain VFCs of a single type through one source from a single manufacturer.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. Comply with NFPA 70.
- E. Product Selection for Restricted Space: Drawings indicate maximum dimensions for VFCs, minimum clearances between VFCs, and adjacent surfaces and other items. Comply with indicated maximum dimensions and clearances.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver VFCs in shipping splits of lengths that can be moved past obstructions in delivery path as indicated.
- B. Store VFCs indoors in clean, dry space with uniform temperature to prevent condensation. Protect VFCs from exposure to dirt, fumes, water, corrosive substances, and physical damage.
- C. If stored in areas subject to weather, cover VFCs to protect them from weather, dirt, dust, corrosive substances, and physical damage. Remove loose packing and flammable materials from inside controllers; install electric heating of sufficient wattage to prevent condensation.

1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation, capable of driving full load without derating, under the following conditions, unless otherwise indicated:
 - 1. Ambient Temperature: 0 to 40 deg C.
 - 2. Humidity: Less than 90 percent (noncondensing).
 - 3. Altitude: Not exceeding 3300 feet.

1.8 COORDINATION

- A. Coordinate layout and installation of VFCs with other construction including conduit, piping, equipment, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.
- B. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 7 Section "Roof Accessories."
- C. Coordinate features of VFCs, installed units, and accessory devices with pilot devices and control circuits to which they connect.
- D. Coordinate features, accessories, and functions of each VFC and each installed unit with ratings and characteristics of supply circuit, motor, required control sequence, and duty cycle of motor and load.

1.9 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Spare Fuses: Furnish one spare for every five installed, but no fewer than one set of three of each type and rating.

PART 2 - PRODUCTS

- 2.1 MANUFACTURERS
 - A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. ABB
 - 2. Danfoss
- 2.2 VARIABLE FREQUENCY CONTROLLERS
 - A. Description: NEMA ICS 2, IGBT, VFC; listed and labeled as a complete unit and arranged to provide variable speed of an NEMA MG 1, Design B, 3-phase induction motor by adjusting output voltage and frequency.
 - 1. Provide unit suitable for operation of premium-efficiency motor as defined by NEMA MG 1.
 - B. Design and Rating: Match load type such as fans, blowers, and pumps; and type of connection used between motor and load such as direct or through a power-transmission connection.
 - C. Output Rating: 3-phase; 6 to 60 Hz, with voltage proportional to frequency throughout voltage range.
 - D. Unit Operating Requirements:
 - 1. Input ac voltage tolerance of 380 to 500 V, plus or minus 10 percent.
 - 2. Input frequency tolerance of 50/60 Hz, plus or minus 6 percent.
 - 3. Minimum Efficiency: 96 percent at 60 Hz, full load.
 - 4. Minimum Displacement Primary-Side Power Factor: 96 percent.
 - 5. Overload Capability: 1.1 times the base load current for 60 seconds; 2.0 times the base load current for 3 seconds.
 - 6. Starting Torque: 100 percent of rated torque or as indicated.
 - 7. Speed Regulation: Plus or minus 1 percent.
 - E. Isolated control interface to allow controller to follow control signal over an 11:1 speed range.
 - 1. Electrical Signal: 4 to 20 mA at 24 V.
 - F. Internal Adjustability Capabilities:
 - 1. Minimum Speed: 5 to 25 percent of maximum rpm.
 - 2. Maximum Speed: 80 to 100 percent of maximum rpm.
 - 3. Acceleration: 2 to a minimum of 22 seconds.
 - 4. Deceleration: 2 to a minimum of 22 seconds.
 - 5. Current Limit: 50 to a minimum of 110 percent of maximum rating.

- G. Self-Protection and Reliability Features:
 - 1. Input transient protection by means of surge suppressors.
 - 2. Under- and overvoltage trips; inverter overtemperature, overload, and overcurrent trips.
 - 3. Motor Overload Relay: Adjustable and capable of NEMA ICS 2, Class 20 performance.
 - 4. Notch filter to prevent operation of the controller-motor-load combination at a natural frequency of the combination.
 - 5. Instantaneous line-to-line and line-to-ground overcurrent trips.
 - 6. Loss-of-phase protection.
 - 7. Reverse-phase protection.
 - 8. Short-circuit protection.
 - 9. Motor overtemperature fault.
- H. Automatic Reset/Restart: Attempts three restarts after controller fault or on return of power after an interruption and before shutting down for manual reset or fault correction. Bidirectional autospeed search shall be capable of starting into rotating loads spinning in either direction and returning motor to set speed in proper direction, without damage to controller, motor, or load.
- I. Power-Interruption Protection: To prevent motor from re-energizing after a power interruption until motor has stopped.
- J. Torque Boost: Automatically varies starting and continuous torque to at least 1.5 times the minimum torque to ensure high-starting torque and increased torque at slow speeds.
- K. Motor Temperature Compensation at Slow Speeds: Adjustable current fall-back based on output frequency for temperature protection of self-cooled, fan-ventilated motors at slow speeds.
- L. Input Line Conditioning: 3% line reactors.
- M. Status Lights: Door-mounted LED indicators shall indicate the following conditions:
 - 1. Power on.
 - 2. Run.
 - 3. Overvoltage.
 - 4. Line fault.
 - 5. Overcurrent.
 - 6. External fault.
- N. Panel-Mounted Operator Station: Start-stop and auto-manual selector switches with manual speed control potentiometer and elapsed time meter.
- O. Indicating Devices: Meters or digital readout devices and selector switch, mounted flush in controller door and connected to indicate the following controller parameters:
 - 1. Output frequency (Hz).

- 2. Motor speed (rpm).
- 3. Motor status (running, stop, fault).
- 4. Motor current (amperes).
- 5. Motor torque (percent).
- 6. Fault or alarming status (code).
- 7. PID feedback signal (percent).
- 8. DC-link voltage (VDC).
- 9. Set-point frequency (Hz).
- 10. Motor output voltage (V).
- P. Control Signal Interface:
 - 1. Electric Input Signal Interface: A minimum of 2 analog inputs (0 to 10 V or 0/4-20 mA) and 6 programmable digital inputs.
 - 2. Remote Signal Inputs: Capability to accept any of the following speed-setting input signals from the BMS or other control systems:
 - a. 0 to 10-V dc.
 - b. 0-20 or 4-20 mA.
 - c. Potentiometer using up/down digital inputs.
 - d. Fixed frequencies using digital inputs.
 - e. RS485.
 - f. Keypad display for local hand operation.
 - 3. Output Signal Interface:
 - a. A minimum of 1 analog output signal (0/4-20 mA), which can be programmed to any of the following:
 - 1) Output frequency (Hz).
 - 2) Output current (load).
 - 3) DC-link voltage (VDC).
 - 4) Motor torque (percent).
 - 5) Motor speed (rpm).
 - 6) Set-point frequency (Hz).
 - 4. Remote Indication Interface: A minimum of 2 dry circuit relay outputs (120-V ac, 1 A) for remote indication of the following:
 - a. Motor running.
 - b. Set-point speed reached.
 - c. Fault and warning indication (overtemperature or overcurrent).
 - d. PID high- or low-speed limits reached.
- Q. Communications: Provide an RS485 interface allowing VFC to be used with an external system within a multidrop LAN configuration. Interface shall allow all parameter settings of VFC to be programmed via BMS control. Provide capability for VFC to retain these settings within the nonvolatile memory.

- R. Integral Disconnecting Means: NEMA KS 1, fusible switch with lockable handle.
- S. Isolating Switch: Non-load-break switch arranged to isolate VFC and permit safe troubleshooting and testing, both energized and de-energized, while motor is operating in bypass mode.
- T. Remote Indicating Circuit Terminals: Mode selection, controller status, and controller fault.
- 2.3 ENCLOSURES
 - A. NEMA 1.
- 2.4 ACCESSORIES
 - A. Devices shall be factory installed in controller enclosure, unless otherwise indicated.
 - B. Push-Button Stations, Pilot Lights, and Selector Switches: NEMA ICS 2, heavy-duty type.
 - C. Stop and Lockout Push-Button Station: Momentary-break, push-button station with a factoryapplied hasp arranged so padlock can be used to lock push button in depressed position with control circuit open.
 - D. Control Relays: Auxiliary and adjustable time-delay relays.
 - E. Standard Displays:
 - 1. Output frequency (Hz).
 - 2. Set-point frequency (Hz).
 - 3. Motor current (amperes).
 - 4. DC-link voltage (VDC).
 - 5. Motor torque (percent).
 - 6. Motor speed (rpm).
 - 7. Motor output voltage (V).
 - F. Historical Logging Information and Displays:
 - 1. Real-time clock with current time and date.
 - 2. Running log of total power versus time.
 - 3. Total run time.
 - 4. Fault log, maintaining last four faults with time and date stamp for each.

2.5 FACTORY FINISHES

A. Finish: Manufacturer's standard paint applied to factory-assembled and -tested VFCs before shipping.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, surfaces, and substrates to receive VFCs for compliance with requirements, installation tolerances, and other conditions affecting performance.
- B. Examine roughing-in for conduit systems to verify actual locations of conduit connections before VFC installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Select features of each VFC to coordinate with ratings and characteristics of supply circuit and motor; required control sequence; and duty cycle of motor, controller, and load.
- B. Select horsepower rating of controllers to suit motor controlled.

3.3 INSTALLATION

- A. Anchor each VFC assembly to steel-channel sills arranged and sized according to manufacturer's written instructions. Attach by bolting. Level and grout sills flush with mounting surface.
- B. Install VFCs on walls.
- C. Comply with mounting and anchoring requirements specified in Division 26 Section "Electrical Supports and Seismic Restraints."
- D. Controller Fuses: Install fuses in each fusible switch. Comply with requirements in Division 26 Section "Fuses."

3.4 IDENTIFICATION

- A. Identify VFCs, components, and control wiring according to Division 26 Section "Electrical Identification."
- B. Operating Instructions: Frame printed operating instructions for VFCs, including control sequences and emergency procedures. Fabricate frame of finished metal, and cover instructions with clear acrylic plastic. Mount on front of VFC units.

3.5 CONTROL WIRING INSTALLATION

- A. Install wiring between VFCs and remote devices according to Division 26 Section "Conductors and Cables."
- B. Bundle, train, and support wiring in enclosures.
- C. Connect hand-off-automatic switch and other automatic-control devices where applicable.
 - 1. Connect selector switches with control circuit in both hand and automatic positions for safety-type control devices such as low- and high-pressure cutouts, high-temperature cutouts, and motor overload protectors.

3.6 CONNECTIONS

- A. Conduit installation requirements are specified in other Division 26 Sections. Drawings indicate general arrangement of conduit, fittings, and specialties.
- B. Ground equipment according to Division 26 "Grounding and Bonding."

3.7 FIELD QUALITY CONTROL

- A. Prepare for acceptance tests as follows:
 - 1. Test insulation resistance for each enclosed controller element, bus, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to perform the following:
 - 1. Inspect controllers, wiring, components, connections, and equipment installation. Test and adjust controllers, components, and equipment.
 - 2. Report results in writing.
- C. Perform the following field tests and inspections and prepare test reports:
 - 1. Perform each electrical test and visual and mechanical inspection, except optional tests, stated in NETA ATS. Certify compliance with test parameters.
 - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

3.8 ADJUSTING

A. Set field-adjustable switches and circuit-breaker trip ranges.

3.9 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain variable frequency controllers. Refer to Division 1 Section "Demonstration and Training."

END OF SECTION 232923

SIEMENS

SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION

3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES

PHONE: 317-293-8880 FAX: 317-293-0374

04/25/25

FOR INFORMATION CONTACT ERIC HUGHES

ENGINEERING DATA FOR IU - MCNUTT CENTRAL RENO

EXISTING APARTMENT BLOOMINGTON IU PROJECT #20241429, IN USA

440P-397692

SPRINGPOINT ARCHITECT

ENGINEER

CONTRACTOR

GENERAL NOTES FOR CONTROLS INSTALLATION CONTRACTOR (CIC)

- 1. All work shall be performed in accordance with the contract documents and all applicable codes and standards.
- 2. Provide and install all wiring, conduit, circuit breakers, etc., and any needed mounting hardware to install control devices/panels (brackets, extensions, stands, etc.) for a complete installation.
- 3. Mount, wire and pipe (control pneumatics) all devices including panels, sensors, relays, actuators, switches, sensor covers/guards, etc. for a complete installation.
- 4. All installation of the energy management system and components is by the CIC unless noted otherwise.
- 5. IU,IUI,IUK,IUE., through Siemens Building Technologies, Inc., will provide all system controllers, relays, transformers, sensors, prefabricated auxiliary panels and switches unless otherwise noted. The CIC will provide all installation materials necessary to mount, install, and wire all controls devices.
- 6. All devices to be installed according to manufacturer's recommendations and the contract documents. Field verify exact locations of all devices/equipment. Coordinate with Siemens.
- 7. All routings for electrical installation are to be verified by the CIC.
- 8. C.I.C. shall be responsible for interlock wiring between VFDs and local disconnect switches, where applicable.
- 9. C.I.C. shall coordinate their work with Siemens, the Contractor, other Subcontractors, and the Owner.
- 10. All control devices and panels that require 120V power that are not powered by the division 26 contractor shall require a dedicated circuit from its own breaker. Provide circuit breakers and power wiring where required.
- 11. Mount panels on racks when wall space is not available. The engineer shows panel locations on HVAC drawings. Actual panel locations are to be coordinated with the contractors and owner.
- 12. All line voltage wiring shall be installed in conduit.
- 13. All wiring must be pulled in one length. Splicing is not allowed. All Control wiring shall be continuous.
- 14. All wiring in mechanical rooms, concealed and inaccessible places and/or where required by project plans and specifications shall be installed in conduit.
- 15. Any conductor carrying voltage greater than 24VAC shall not occupy the same conduit as low voltage wiring.
- 16. Conduits installed outdoors or encased in concrete shall be in rigid conduit.
- 17. Open cable shall be installed only where space is accessible and allowed by the project plans and specifications. In these cases, cable shall be rated for space they occupy. Provide plenum rated materials as required.
- 18. See specifications and IU PPA Control Design Standard document for conduit use & installation requirements.
- 19. Provide as-built record drawings of installation of the system.
- 20. Record drawings shall include routing and sizing of communications wiring, sensor wiring, power trunk wiring, transformer locations, field device locations, etc.
- 21. C.I.C. shall receive, handle, and store, as needed, all material to be installed under their contract. Subcontractor shall be responsible for verification of quantity received. The CIC will be responsible for verifying all received material. Discrepancies must be immediately documented with the shipping company prior to their leaving the delivery site and shall be reported in writing to Siemens Building Technologies, Inc. within 48 hours. The CIC is responsible for the security of all materials received and stored. The CIC will replace, at his expense, any materials missing or damaged.
- 22. Provide and install all tags and labels per plans and specifications for all control devices. Coordinate tag and label text, size and type with Siemens. Tag wiring at the field panel with the full point <u>name</u>. Tag wiring at the field device with the full point <u>address</u>.
- 23. Terminate all wiring. If necessary, CIC will make all cutover terminations under the supervision of Siemens Building Technologies at startup, unless otherwise directed by Siemens.
- 24. CIC is responsible for participating in the commissioning process to the extent that it involves their installation work.
- 25. For wire runs to devices that require 24 VAC such as electric valve actuators, electric damper actuators, sensing devices, etc., CIC shall use the following wiring arrangement:
 - a. For devices that use a three-wire arrangement per the control drawings for carrying the 24VAC power and signal to the device, install cable type 18-gauge 3 conductor (18-3C) unless otherwise noted on control wiring diagrams. Neutral is tied together at the auxiliary panel.
 - b. For devices that use a four-wire arrangement per the control drawings for carrying the 24VAC power and signal to the device, use the following cable types unless otherwise noted on control wiring diagrams.
 - i. Install cable type 14-gauge 2 conductor (14-2C) for the 24VAC powering the device.
 - ii. Install cable type 18-gauge 2 conductor (18-2C) for the signal controlling the device.
 - iii. Tie neutrals together at the device.
 - c. QPA and Q series sensors may be landed to the RTS port on the BACnet TEC controller and will have a preterminated wire in either 50- or 100-foot length. See individual drawing details for further information.
- 26. C.I.C. shall use control wire according to the following schedule. Purchase wire manufactured by one of the following three vendors or approved equal. If wire size is not specified coordinate with Siemens and plan on using 12 gauge.
- 27. Minimum conduit size: 3/4".
- 28. Control wiring concealed in walls will be in EMT conduit. Existing wall will be 3/4" flex if inaccessible.
- 29. Wire size for terminal equipment devices will be either 18 AWG 2 conductor or 18 AWG 3 conductor wire unless otherwise noted or providing power to the TEC.

Anixter

Description	Part Number	Application
ETHERNET 23AWG, CAT6	CMP-00424AVA-7-06	Ethernet Network Communication cabling
		(verify type/color)
24-1p (STR) SHD Cable-Plenum	H-B-TSP24LC-CMP	BLN trunks
24-1p (STR) SDH Cable-Plenum	H-F-TSP24LC-CMP	FLN trunks
24-1.5p (STR) FT-6 Cable-Plenum	H-F-1.5TSP24LC-CMP	MSTP FLN BACnet trunks
20-2c (Solid) Cable-Plenum	KNX-TSP20LC-CMP	KNX Cable for DXR
18-2c (STR) Cable-Plenum	H-TP18-CMP	Point/low voltage wiring
18-3c (STR) Cable-Plenum	H-3C18-CMP	DXR/TEC actuators, transducers
18-6c (STR) Cable-Plenum	1806C-2-2N-01	Point/low voltage wiring
14-2c (STR) Cable-Plenum	H-2C14-CL3P	24VAC power trunk/power for devices

Anixter Contact: Gina Menolascino, Siemens Industry Account Manager 888-479-3830 2301 Patriot Blvd. Glenview, IL, 60026 sbt@anixter.com

Belden

Description	Part Number	Application
ETHERNET 23AWG, CAT6	2413F D151000	Ethernet Network Communication cabling
		(verify type/color)
24-1p (STR) SHD Cable-Plenum	YR48881 0031000 (CMP)	BLN trunks
24-1p (STR) SDH Cable-Plenum	YR49243 2121000 (CMP)	FLN trunks
24-1.5p (STR) FT-6 Cable-Plenum	SPECIAL ORDER WIRE	MSTP FLN BACnet trunks
20-2c (Solid) Cable-Plenum	SPECIAL ORDER WIRE	KNX Cable for DXR
18-2c (STR) Cable-Plenum	YM48514 0061000	Point/low voltage wiring
18-3c (STR) Cable-Plenum	YM48447 0061000	DXR/TEC actuators, transducers
18-6c (STR) Cable-Plenum	SPECIAL ORDER WIRE	Point/low voltage wiring
14-2c (STR) Cable-Plenum	YM48515 0131000	24VAC power trunk/power for devices

Belden Contact: Communications Supply Corporation 317-266-1600 1560 Indiana Avenue, Indianapolis, IN 46202 buybelden@gocsc.com

The Cable Company

Description	Part Number	Application
ETHERNET 23AWG, CAT6	5652P66CMP1000	Ethernet Network Communication cabling (verify type/color)
24-1p (STR) SHD Cable-Plenum	5200BLN	BLN trunks
24-1p (STR) SDH Cable-Plenum	5200FLN	FLN trunks
24-1.5p (STR) FT-6 Cable-Plenum	5201P67FLN1000	MSTP FLN BACnet trunks
20-2c (Solid) Cable-Plenum	5212-P47KNX1003	KNX Cable for DXR
18-2c (STR) Cable-Plenum	5041SBT	Point/low voltage wiring
18-3c (STR) Cable-Plenum	5043SBT	DXR/TEC actuators, transducers
18-6c (STR) Cable-Plenum	5046P33CMP	Point/low voltage wiring
14-2c (STR) Cable-Plenum	5061SBT	24VAC power trunk/power for devices

TCC Contact: Caitlin/Bart 800-677-9473 498 Bonnie Lane, Elk Grove Village, IL 60007 ilsales@tccwire.com

- 30. CIC shall create and keep an up to date list of DXR Bar Codes in a binder that is accessible to Siemens. CIC will create a list of terminal equipment that is controlled by DXR Controllers. CIC will remove the Bar Code from the DXR Controllers at the time of controls installation for each DXR and affix the Bar Code next to the associated Terminal Equipment Name in the DXR Bar Code Binder. CIC will scan the information and transmit in .pdf format to Siemens upon request.
- 31. CIC installation verification list. CIC shall create and keep an up to date list of the status of Mechanical System and Terminal Equipment controls installation in a binder that is accessible to Siemens. CIC will update Siemens weekly with the status of controls installation for each Mechanical System and each piece of Terminal Equipment.

DWG | DESCRIPTION

GENERAL

CVRST	COVER SHEET
CIC	C.I.C CONTRACTOR NOTES
LEG	Legend & Abbreviations
ABAC	Anixter Building Auto. Cables
ALN	ALN WIRING SPECIFICATIONS
FWIRE	FLN WIRING SPECIFICATIONS
PTRM1	PXCC Termination Specification
PTRM2	PXCC Termination Spec. Sheet 2
PWIR	PXCC Wiring Specification
	5 1
	SCHEDULE

- VLV CONTROL VALVE SCHEDULE
- DXR DXR FLN DEVICE SCHEDULE


CONTROL DRAWINGS

R01 SYSTEM RISER R01A SYSTEM RISER BOM R02 PNL-7 MSTP DXR NETWORK R02A PNL-7 MSTP DXR NETWORK BOM 100 AHU-6 CONTROL AHU-6 ELEC. WIRING 1 100A 100B AHU-6 ELEC. WIRING 2 AHU-6 ELEC. WIRING 3 100C 100D AHU-6 AUX PANEL LAYOUT 100E AHU-1 CONTROL BOM & SOO VAV BOX W REHEAT COIL 400 400A VAV BOX W REHEAT BOM & SOO 401 VAV BOX W RHT COIL, NO LCD 401A VAV BOX W REHEAT BOM & SOO

DDC PANEL LAYOUTS


- E100 PXCC-7 AHU-6
- E100A PXCC-7 AHU-6 BOM

REVISION HISTORY 0 4/25/2025 HB SUBMITTAL SET	SIEMENS	3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268	IU - MCNUTT CENTRAL RENO IU PROJECT #20241429, IN	4
	SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION	UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	ENGINEER HBDRAFTER HBCHECKED BY CHECKED BY 04/25/25INITIAL RELEASE 04/25/25LAST EDIT DATE O4/25/25Table of Contents	
© Copyright 1994-2025 Siemens Industry Inc. All rights reserved				




© COPYRIG	HT 1994-2025 SIEME	ENS INDUSTRY INC. ALL RIGHTS RESERVED	SIEMENS INE SMART INFR	USTRY INC. ASTRUCTURE DIVISION	PHONE: 317-293-8880 FAX: 317-293-0374	Legend & A		04/25/ ONS
	/25/2025				SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES	IU PROJECT #2	O241429, IN	J NITIAL REL
		HISTORY			POINT NUM			ENO
				NOTE OR REVISION XX PAGE REFERENCE	NODE NUME FLN TRUNK DROP NUME ROINT NUME	BER		
DR	OP NUMBER INT NUMBER	DROP NUMBER	DETAIL	XX STANDARD DDC TER	REFERENCE			READ A DIGITAL
CA	UNK NUMBEF BINET NUMB N TRUNK	R TRUNK NUMBER K_	TO CONTROL DEVICE	PNEUMATIC TERMINA	LOGICAL PO	INT NAME – AH1LTD [0001: 3.10	0.27	
		PTNAME [0]00]00]00 PTNAME [0]00]000 PTNAME PTNAME [0]00]000 PTNAME PTNAME [0]00]000 PTNAME PTNAME [0]00]000 PTNAME [0]00]000 PTNAME [0]00]000 PTNAME [0]00]000 PTNAME [0]00]000 PTNAME [0]00]000 [0]		ELECTRICAL TERMINA	POINT NU	IMBER]	
	HE	HUMIDIFIER ELECTRIC		DETAILS	CABINET FLN TRUI DROP NU	NUMBER		
	G GD H	GAUGE GAS DETECTOR HYGROSTATS	RC	RECEIVER CONTROLLER	BLN NUM			— READ — DIGIT
	FM FMS FS FTP	FLOW MIR. (FLOW METER STATION) FIRE MGMT. SYSTEM FLOW SWITCH FLOW TRANSMITTER PNEU.	PXCC PXCM PXG3 RBC	PX COMPACT CONTROLLE PXC-MODULAR CONTROLL BACNET ROUTER ETHERN REMOTE BUILDING CONTR	LER IETIP-MS/TP LOGICAL	POGEE: PII – EXAMPLE POINT NAME – AH1LTD [0.10.3.1	0.27	<u> </u>
	EXP FAN FHC FM	EXPANSION PANEL FAN FUME HOOD CONTROLLER FLOW MTR. (FLOW METER STATION)	PTP PTR PV PXCC	PRESSURE TRANSMITTER PRINTER PILOT VALVE PX COMPACT CONTROLLE				IKAN
	EP ES ET EXP	ELECTRO–PNEUMATIC VALVE END SWITCH ENTHALPY TRANSMITTER EXPANSION PANEL	PST PT PTE PTP	PULL STATION PITOT TUBE PRESSURE TRANSMITTER PRESSURE TRANSMITTER			W WST XDR XFMR	WELL WEAT TRAN TRAN
	DPU DXR EC	DIGITAL POINT UNIT TERMINAL EQUIPMENT CONTROLLER ENTHALPY COMPARITOR ELECTRO, PNELMATIC VALVE	PRV PS PSE PST	PRESSURE REDUCING VAI POSITIONING SWITCH POSITION SENSOR ELECTE			VAC VB VTE	VARI, VIBR, VELO
	DPS DPTE DPTP	DIFFERENTIAL PRESSURE SWITCH DIFF. PRESS. TRANSMITTER ELEC. DIFFERENTIAL PRESSURE PNEUMATIC	PNL PPM PRC DDV	PANEL POINT PICKUP MODULE PRESSURE REG. CONTROL			V V* VA	VALV VALV TEC
	DEM DP DPR	DEMAND ENERGY MONITOR DEW POINT TRANSMITTER DIFFERENTIAL PRESS. REGULATOR	PE PL PM	PRESSURE ELECTRIC SWI PILOT LIGHT POWER MONITOR	ICH			UNIT UNIT UNIT
	CVC D DDC	CONSTANT VOLUME CONTROLLER DAMPER DUAL DUCT CONTROLLER	P PA PCT	PUMP PULSE ACCUMULATOR PROGRAMMABLE CLOCK			TTE TTP TXIO	TEMP TEMP TX-I
	CS CT CTTE	CURRENT SWITCH CURRENT TRANSDUCER CO2 TEMP TRANSMITTER ELEC	OCCB OBS ODP	OCCUPANCY AND BRIGHT OBSOLETE OPERATOR DATA PANEL	NESS		TIE TIU TMR	TRUN TELC TIMEF
	CP CPU CRT	COMPONENT PANEL CENTRAL PROCESSING UNIT CATHODE RAY TUBE	MPU MS OCC	MULTI-POINT UNIT MOTOR STARTER OCCUPANCY			TEC TH TI	TERM THER TRUN
	CBL CKV CM	CABLES CHECK VALVE CONSTRUCTION MATERIALS	ME MEC MG	ELECTRONIC ACTUATOR MODULAR EQUIPMENT CO MAGNEHELIC GAUGE	NTROLLER		TCU TDR TE	TERM TIME THER
	BRTT BTN	BRIGHTNESS AND TEMPERATURE BUTTON	MBC MDM	MODULAR BUILDING CONT MODEM	TROLLER		TBC TC	TERM TEMF
	BIM BOIL BRT	BUS INTERFACE MODULE BOILER BRIGHTNESS	LTDE LTDP LUI	LOW TEMP. DETECTOR EL LOW TEMP. DETECTOR PN LOCAL USER INTERFACE	ECTRIC		SV SW T	SOLE SWIT ROOM
	AZM BCU BELL	AUTOZERO MODULE BUS COUPLING UNIT BELL	LLS LLT LPR	LIQUID LEVEL SWITCH LIQUID LEVEL TRANS. POWER SUPPLY 24VAC/2			SPKR SPP SPR	SPEA STAT STAT
	AT ATD ATEC	AUTOMATIC TRAP AUTO TANK DRAIN ACTUATOR TEC	KWM LA LC	ELECTRIC KILOWATT METE LIGHT ACTUATOR LIMIT CONTROLLER (LIMIT			SE SIO SLX	SWITO SLX APOO
	AOP AP APS	ANALOG OUTPUT, PNEUMATIC ACTUATOR PNEUMATIC AUX. POWER SUPPLY	HTE HTP INT	HUMIDITY TRANSMITTER E HUMIDITY TRANSMITTER F INTERCOM	PNEUMATIC		SC SCU SD	STEP STAN SMOł
	AEM AF AFS	APOGEE ETHERNET MICROSERVER AIR FILTER AIR FLOW STATION	HORN HPC HTD	HORN HEAT PUMP CONTROLLER HIGH TEMPERATURE DETE	ECTOR		RV S/W SA	RELIE SOFT SHAE
	AD ADXR AE	AIR DRYER ACTUATOR DXR ACTUATOR ELECTRIC	HL HMI HOA	high limit gamma touch panel hand-off-auto switch	4		RE RP RS	RELA RELA REST
	SYMBOL AC	DESCRIPTION AIR COMPRESSOR	SYMBOL HHC	DESCRIPTION HAND-HELD OPERATOR'S	5 TERMINAL		SYMBOL RCU	DESC REMO
	CONTROL	CONTROL SYMBOL	CONTROL	CONTROL SYMBOL			CONTROL	CON

CONTROL SYMBOL DESCRIPTION REMOTE CONTROL UNIT RELAY ELECTRIC RELAY PNEUMATIC RESTRICTOR RELIEF VALVE SOFTWARE SHADE ACTUATOR STEP CONTROLLER STAND ALONE CONTROL UNIT SMOKE DETECTOR SWITCH ELECTRIC SLX IO MODULES APOGEE SLX CONTROLLER SPEAKER STATIC PRESSURE PROBE STATIC PRESSURE REGULATOR SOLENOID VALVE SWITCH PNEUMATIC ROOM THERMOSTAT, PNEUMATIC TERMINAL BOX CONTROLLER TEMPERATURE CONTROLLER(S200) TERMINAL CONTROL UNIT TIME DELAY RELAY THERMOSTAT, ELECTRIC TERMINAL EQUIPMENT CONTROLLER THERMOMETER TRUNK INTERFACE TRUNK ISOLATOR EXTENDER TELCOM INTERFACE UNIT TIMER, TIME CLOCK TEMPÉRATURE TRANSMITTER ELECTRIC TEMPERATURE TRANSMITTER PNEUMATIC TX-I/O FAMILY CONTROLLER MODULES UNITÁRY CONTROLLER UNIT CONDITIONER CONTROLLER UNIT VENT CONTROLLER VALVE VALVE SERVICE PARTS TEC VALVE ACTUATOR VARIABLE AIR VOLUME CONTROLLER VIBRATION ISOLATOR VELOCITY TRANSMITTER ELECTRICAL WELL WEATHER STATION TRANSDUCER TRANSFORMER ---- DIGITAL INPUT READ AS " SEE PAGE 5A FOR MORE DETAIL " DIGITAL INPUT RENO 44OP397692 0 INITIAL RELEASE | LAST EDIT DATE LEG 04/25/25 04/25/25



XXX TWISTED PAIR			
TWISTED PAIR			
TWISTED PAIR			
<u>[P)</u>			
AT 1KHz, 1MHz D OR BETTER			
NIXTER CABLE PART			
6B).			
ECIFICATIONS			
TWISTED PAIR			
SHIELD			
SHIELD			
OR LESS			
ANIXTER CABLE PART 6B).			
DSER THAN 5 FEET TO A VARI	ABLE FREQUE THE VFD. NE	NCY DRIVE (\ TWORK ENTR`	/FD) Y
SEPERATE CONDUIT AND ALL HIGH POWER CABLING IN THE	NEIWORK WIR	ING MUST BE	
ER THAN 5 FEET FROM CONDU POWER CABLES (AT A DISTANCE	E OF 5 FEET)	AT A 90' AT	NGLE.
AYS WITH CIRCUITS CARRYING POWER CABLES.	20 AMPS SHO	OULD BE NO	CLOSER
S WITH CONDUITS CARRYING O' HIGHER POWER CABLES.	VER 20 AMPS	SHOULD BE	NO
HIGHER FORER CABLES.			
NO		440P397	692
		0	
ITIAL RELEASE LAST EDIT D	ATE	AI	
04/25/25 04/25/2	5	μ	
-			



LE SPECIFICATIONS	
XXXXX TWISTED PAIR	
ANCE OR LESS	
BERS	
24LC-CMPBX-P HAWG,STR,TSP,LOCAP,CMP (FT-6)	
CABLE SPECIFICATIONS	
TWISTED PAIR REFERENCE WIRE SHIELD	
ANCE CONDUCTOR TO CONDUCTOR. FANCE CONDUCTOR TO SHIELD.	
CH LAY WITH TWISTED PAIR	
DRAIN WIRE	
BERS	
SP24LC-CMP-Y STR TC FFEP FT6 SHD YEL (FT-6)	
STR FT6 ORG (FT-6)	
G CLOSER THAN 5 FEET TO A VARI THE NETWORK MUST CONNECT TO THA SEPERATE CONDUIT AND ALL ROM HIGH POWER CABLING IN THE	ABLE FREQUENCY DRIVE (VFD) THE VFD. NETWORK ENTRY NETWORK WIRING MUST BE DRIVE.
CLOSER THAN 5 FEET FROM CONDU GH POWER CABLES (AT A DISTANCE	ITS CARRYING 100KVA OR COF 5 FEET) AT A 90° ANGLE.
E TRAYS WITH CIRCUITS CARRYING : HER POWER CABLES.	20 AMPS SHOULD BE NO CLOSER
TRAYS WITH CONDUITS CARRYING ON THE HIGHER POWER CABLES.	/ER 20 AMPS SHOULD BE NO
NO	44002000
	44OP397692 0
TIAL RELEASE LAST EDIT DATE	
4/25/25 04/25/25	FWIRE
CATIONS	a w w a a a damaa

PXCC	WIRING	TYPE AND GAUG TABLE 1	e requireme	<u>-NTS</u>	<u>M</u> .	AXIMUM DO) WIRE RU table 3	N LENGHT	<u>S</u>	
CIRCUIT TYPE	CLASS	WIRE TYPE	MAX. DISTANCE	CONDUIT SHARING	, 2 NOMINAL	STARTER		WIRE SIZE		
AC LINE POWER ¹	POWER	#12-14 THHN	REFER TO NEC	CHECK LOCA CODES		SIZE	<i>#</i> 18	<i>#</i> 16	#14	SERVICE BOX MAX
DIGITAL OUTPUT	1&2	TP not required, check job specs & local codes #18 to #24 AWG	s SEE TABLE 3	CHECK LOCA CODES	L 200 VA	0	500ft (152m)	900ft (274m)	1400ft (427m)	VOLTAGE: 102-132 VAC 204-264 VAC
DIGITAL INPUT	2	TP not required, check job specs & local codes	750ft (230 m)	CHECK LOCA CODES		2	200ft (61m) 100ft	300ft (91m) 150ft	500ft (152m) 250ft	LINE FREQUENCY: 50 / 60 Hz XFMR POWER: 200 VA (MAX.) 115V OUTLETS: 200 VA (MAX.)
ANALOG INPUT ⁴ 100K/10K Thermistor	2	#18 to #24 AWG #18-#24 TP ^{3.6} r TSP ⁵ CM(FT4) or CMP(FT6	750ft (230 m)	CHECK LOCA	L 1150 VA	3	(30m) 70ft	(46m) 100ft	(76m) 200ft	$\frac{\text{KNOCKOUT TYPES}}{\text{A}=1^{n} \underbrace{\&} 1-1/4^{n}} \\ \text{Pxcc SMALL ENCL.} $
ANALOG INPUT ⁴ 1K Ni OR RTD	2	#18-#24 TP ^{3,6} or TSP ⁵ CM(FT4) or CMP(FT6	750ft (230 m)	CHECK LOCA		ES:	(21m)	(30m)	(61m)	$B=3/4" \& 1" \\ C=1/2" \& 3/4" \\ \hline$
ANALOG INPUT 0-10 V	2	#18-#24 TP ^{3,6} r TSP ⁵ CM(FT4) or CMP(FT6)	750ft (230 m)	CHECK LOCA	1. DISTANCE	ROSS THE	wire for A			P1 PXCC CONDUIT PENETRATIONS
ANALOG INPUT 4-20 mA	2	#18-#24 TP ^{3,6} or TSP ⁵ CM(FT4) or CMP(FT6	750ft (230 m)	CHECK LOCA	4A @ 200	OVAC & 30	VDC			PRCC FAMILY VA RATINGS & SENSOR SUPPLY
ANALOG OUTPUT 0-10 V	2	#18-#24 TP ^{3,6} or TSP ⁵ CM(FT4) or CMP(FT6	750ft (230 m)	CHECK LOCA CODES		OTOR STAR ENGTHS SHO		OR 120VOL	TS.	PRODUCT24VACVARATING24VDCMAPXCOMPACT1618100PXCOMPACT2420100
ANALOG OUTPUT 4-20 mA	2	#18-#24 TP ^{3,6} TSP ⁵ CM(FT4) or CMP(FT6	750ft) (230 m)	CHECK LOCA CODES	MAXIMUM N	IUMBER HS		ries on <i>a</i>	<u>LN TRUNK</u> 6	PX COMPACT 24 20 100 PX COMPACT 36 35 200
ETHERNET ALN	2	#24 (4) TP ⁶ CAT5 OR BETTER	295ft (90 m)	CHECK LOCA CODES		1200	TABLE 4 4800	9600 - 38.4	<57.6K - 115.2K	
ALN TRUNK	2	#24 TSP	SEE TABLE 4	CHECK LOCA CODES	L SERIES TIE	BAUD 'S 10	BAUD 7	BAUD 6	BAUD	NOTES: 1. NO MORE THAN SEVEN (7) FULLY LOADED PXCC CABINETS ALLOWED ON A SINGLE 3-WIRE CIRC
. WHEN DAISY-CH	AINING	24VAC POWER TO	CONTROLLERS	S USE #14 WIF	RE. ALN TRUNK DISTANCE	4000ft (1.2km		4000ft (1.2km)	3280ft (1km)	2. RECEPTACLE IS PRE-WIRED AND MOUNTED IN FACTORY, FOR 115VAC SERVICE BOX ONLY.
CLASS 2 WIRE IS N 75°C OR HIGHER). ALSO UL LISTED AI 3. TWISTED PAIR, N CAN BE USED IN P 75°C OR HIGHER) (SEE THE FIELD PUF ACCORDINGLY FOR 5. SHIELDED TWISE NOISE LEVELS UPT NEEDED.TERMINATE 5. FOR 24AWG INS ANSI/TIA/EIA-568- 30XES. USE STRAM	NEC TYPE NEC TYPE NEC TYPE NON-JAC PLACE OF CABLE WI RCHASING FFECTS F EACH W TED PAIF O 10 V/ SHIELD TALL CA -B.1 OR IDED CC m) TO C	ISTED 300V 75°C(1 E CM (FT4) (75°C (PE CL2 AND CL2P (ED 300V 75°C (16° CKETED UL LISTED 7 F CM(FT4) OR CMP(HEN CONTAINED IN G GUIDE FOR WIRE. POINT INTERCEPT EI IRE GAUGE AND SE R (TSP) IS NOT RE(M. AT HIGHER LEVE ON ENCLOSURE AN TEGORY5 OR BETTE HIGHER. USE SOLIE OPPER PATCH CABL CONNECT SWITCH OF TABLE 2	DR HIGHER) C IS NOT ACCE 7'F) OR HIGHE (FT6)(BOTH M CONDUIT PEF NTRY. ADJUS NSOR TYPE. QUIRED FOR E LS TSP MAY D TAPE BACK COPPER BE COPPER BE LES 13ft (4m)	R CMP(FT6) PTABLE UNLES R ND 300V, CAE UST BE RATE CLOCAL CODE T INTERCEPT CLECTRICAL BE ON POINT E TWEEN JACK	GENERAL NOIE GENERAL NOIE COMPLY WITH SIZE WIRE FOI ALL WIRE TO APPLICATION BY ALWAYS REFE WIRING MUST CIRCUIT IN CONE THE ALN TRU CABINETS. NO S CM/CMP/MM/	DISTANCE A LOCAL BUI R LOAD, CL BE APPROV AGENCIES R TO LOCA HAVE INSU DUIT. NK MUST B SPLICES ALL (MMP WIRE D TEMPERA	APPLIES TO LDING CODE IRRENT, AN /ED OR LIS' SUCH AS U L CODES FI LATION RA E AN UNIN LOWED. IS NOT US/ TURE INSTA	ES ID VOLTAGE TED FOR TI JL, NEC, C: OR CONDUI TED FOR H TERRUPTED ABLE FOR 1 ALLATIONS	:. HE INTENDED SA. T SHARING. IGHEST VOLTAGE RUN BETWEEN CLASS 1	 P2 PXCC POWER WIRING 00 NOTES: 1. COMMUNICATION CONNECTORS PLUG INTO PXCC. 2. ALN MUST BE DAISEY-CHAINED WHEN RUNNING 19.2 k BAUD OR FASTER AND TRUNK TERMINATORS USED AT BOTH ENDS OF LINE P3C. 3. TERMINATE SHIELD AT LEAVING END OF ALN TRUNK ONLY. 4. USE ALN SHIELD TERMINATION P3A WHEN 24VAC E TERMINAL IS EARTH GROUNDED. 5. USE ALN SHIELD TERMINATION P3B WHEN 24VAC E TERMINAL IS OPEN. A: ALN TRUNK + - + WIRE SECURING CONNECTOR
PACC WIRE SPECIFIC		GE POINT APPLICATIONS	POINT USAGE		ALN TRUNK	EALN				SHLD REFER TO
CABLE CONFIGURATION		PAIR OR TSP	TWISTED PAIR (UNJ	ACKETED) OR TSP	TWISTED SHIELDED PAIR		STED PAIR			GUIDELINES
GAUGE	#18 TO	#22 AWG (STRANDED)	#18 TO #22 AV	/G (STRANDED)	24 AWG (STRANDED)	24AWG(STRANDED)			B: ALN TRUNK + - + WRE SECURING PANELS AN CONTROLLE
	n.a.		n.a.		12.5 pf/ft OR LESS		t OR LESS			CONTROLLE CONTROLLE CONTROLLE FOR FLN W
TWISTS PER FOOT SHIELDS		JM UIRED (IN CASE OF 1% FOIL W/ DRAIN WIRE)	6 MINIMUM NOT REQUIRED (TSP, 100% FOIL		6 MINIMUM 100% FOIL W/ DRAIN WI		RY 5 Min QUIRED			(EOL ONLY)
NEC CLASS		° (75℃ OR HIGHER)	NOT SPECIFIED	,	CM, CMP (75°C OR HIGH	IER) MM, MM	P			SHLD
CEC CLASS		6 (75°C OR HIGHER)	NOT SPECIFIED		FT4, FT6 (75°C OR HIGH	,	ECIFIED			
UL VOLTAGE RATING	NOT SPE	ECIFIED	300 VAC 2		NOT SPECIFIED	NOT SPI	ECIFIED			
UL TEMP. RATING	NOT SPE	ECIFIED	75°C (167°F)		NOT SPECIFIED	NOT SPI	ECIFIED			(P3) PXCC COMMN TERMINATIONS
) WITH A BACKWARDS 'F N FIELD PANELS CONTA			JSE ONLY UL-LISTED WIR	E.				00
						1				

REVISION HISTORY

0 4/25/2025 HB SUBMITTAL SET

SIEMENS


SIEMENS INDUSTRY INC.


UNITED STATES SMART INFRASTRUCTURE DIVISION FAX: 317-293-0374

3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268 ENG PHONE: 317-293-8880

		20241429,	
ENGINEER HB	DRAFTER HB	CHECKED BY	
PXCC	; Wirin	g Spec	ific


© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED





MAXIMUM CONTACT CLOSURE RATE IS 10 PER SECOND DI EXCITATION = 24VDC, 10mA UI, U EXCITATION = 24VDC, 6mA, 150ms, 1mA DI CANNOT BE USED FOR PULSE ACCUMULATION. UI, U, X MAXIMUM PULSE RATE = 20HZ(25ms PER STATE, 50ms PRE PULSE. PXCC DO CONTACT RATINGS AC OPERATION: 4A @ 240VAC (RESISTIVE) 3A @ 240VAC (INDUCTIVE) SIZE 4 MOTOR STARTER DC OPERATION: 40W @ < 50VDC20W @ > 50VDCREFER TO PXCC TERMINATION TABLES FOR ACTUAL POINT ADDRESSES. COMMON TERMINAL MAY BE SHARED BY 2 POINTS. AND ORDER MAY BE REVERSED ON ADJACENT POINTS. REFER TO DRAWING P2 ON PWIR FOR MAXIMUM CURRENT PROVIDED BY THE PXCC 24VDC SENSOR SUPPLY. EXTERNAL POWER SUPPLY CAN EITHER BE A 24VDC POWER SUPPLY OR A 24VAC TRANSFORMER DEPENDING ON THE SENSOR SELECTED. IF NOT AN ISOLATED NC CLASS 2 CIRCUIT THEN POWER SOURCE, NEUTRAL AND PXC COMPACT COMMON MUST BE BOTH CONNECTED TO THE SAME OR BONDED BUILDING APPROVED EARTH GROUND. FOR FURTHER DETAILS SEE EARTH GROUNDING RULES (125-3002) APOGEE WIRING GUIDELINES FOR FIELD PANELS AND EQUIPMENT CONTROLLERS. 50mA OR LESS - 750ft/230m 50mA TO 100mA - 375ft/115m 100mA TO 150mA - 250ft/76m 150mA TO 200mA - 187ft/57m 200mA TO 250mA - 150ft/46m WHERE H TERMINAL IS NOT A NEC CLASS 2 CIRCUIT, RELAY COMMON TERMINAL BRANCH CURRENT MUST BE EXTERNALLY LIMITED TO 10A MAXIMUM BY A NEC APPROVED MEANS. NOT A WHERE REQUIRED, NEUTRAL TERMINAL BRANCH CURRENT MUST BE EXTERNALLY LIMITED BA A NEC APPROVED MEANS. 440P397692

Ω



Point Ad	dress Tab	le for th	e PXC3	6.
	Point Type	_		PXC Point Address
Point Type	Number	-	ninals	
Super Universal	X1	Signal ² 30	Common 31	1
Input/Output (X) ¹	X1 X2	30	31	2
	X3	33	34	2
	X4	35	34	4
	X4 X5	36	34	4 5
	X6	38	37	6
	X7	39	40	7
	X7 X8	41	40	8
Universal	 U9	50	40 51	0 9
Input/Output (U)	U10	52	51	10
,	U11	52	54	10
4 - >	U12	55	54	12
	-			
	U13	56	57	13
	U14	58	57	14
	U15	59	60	15
	U16	61	60	16
	U17	62	63	17
	U18	64	63	18
	U19	65	66	19
	U20	67	66	20
	U21	68	69	21
	U22	70	69	22
	U23	71	72	23
<u> </u>	U24	73	72	24
Digital Input (DI)	DI25	74	75	25
-	DI26	76	75	26
	DI27	77	78	27
Divital Outrait	DI28	79	78	28
Digital Output (DO)	DO29	· ·	5,6	29
\ - <i>/</i>	DO30		3,9	30
	DO31		1,12	31
	DO32		4,15	32
	DO33	· ·	7,18	33
	DO34 DO35	· ·	0,21 3,24	34 35
	DO35		.3,24 6,27	36
	0000	20,2		00

Notes:


1. FOR PRE-PXC24.2 CONTROLLERS, POINTS 13-16 WERE UNIVERSAL I/O POINTS INSTEAD OF THE CURRENT SUPER UNIVERSAL I/O POINTS.

2. FOR THE APPROPRIATE TERMINAL SYMBOL, PLEASE REFER TO THE RESPECTIVE POINT TYPE COLUMN.

3. THE Common TERMNAL IS ALWAYS THE FOLLOWING SYMBOL:

4. SEE BELOW FOR DIGITAL OUTPUT SYMBOL:

C NC L- NO



Siemens Industry, Inc. Job Name: IU - MCNUTT CENTRAL RENOVATION Job Number: 44OP-397692 Revision: 0 Date: 4/24/2025

System: AHU Valves

System. Ar																
Number	Unit ID	Valve Tag	0.4	Product Number	Line Sizes	Valve	onfiguratio	Body	Calculate	Actual Cy	Failaafa	Flow	Design	Actual	Close-Off	Cont
Number		valve lag	Q'ty	Product Number	(in.)	Sizes (in.)	onfiguratio	Style	d Cv	Actual Cv	Failsafe	(GPM)	P.D	P.D	(psi)	Sigr
1	AHU-6	AHU-6 HCV	1	274-03164	1.00	0.50	2W/Sng	Globe	1.79	2.50	NO-SR	4.00	5.00	2.56	250	0-10V
2	AHU-6	AHU-6 CCV	1	274-03167	1.50	1.00	2W/Sng	Globe	8.50	10.00	NO-SR	19.00	5.00	3.61	201	0-10V

Notes:

All control valves and wells shall be installed by the mechanical contractor

Flow units are in GPM (Water) lbs/hr (Steam)

Failsafe Notation: NSR = Non-Spring Return, SR = Spring Return, FS = Failsafe

Valve Configuration Notation: 2W = 2-Way, 3W = 3-Way

Seating Notation: Sng = Single Seated, Dbl = Double Seated

Valve Schedule

	Voltage	Document Number	Comment
ignal	Voltage 24 VAC		Comment
ontrol ignal 10VDC 10VDC		Number	Comment

Siemens Industry, Inc. Job Name: IU - MCNUTT CENTRAL RENOVATION Job Number: 44OP-397692 Revision: 0 Date: 4/24/2025

System: Air Terminal Unit Valves

Number	Unit ID	Valve Tag	Q'ty	Product Number	Line Sizes (in.)	Valve Sizes (in.)	Configuration	Body Style	Calculated Cv	Actual Cv	Failsafe	Flow (GPM)	Design P.D	Actual P.D	Close-Off (psi)	Control Signal	Voltage	Document Number	Comment
1	TU-301	TU-301 RHV	1	259-02034	N/A	0.50	2W/Sng	Globe	0.80	1.00	NO-NSR	1.80	5.00	3.24	120	Floating	24 VAC	155-306P25	
2	TU-302	TU-302 RHV	1	259-02032	N/A	0.50	2W/Sng	Globe	0.45	0.63	NO-NSR	1.00	5.00	2.52	120	Floating	24 VAC	155-306P25	
3	TU-303	TU-303 RHV	1	259-02032	N/A	0.50	2W/Sng	Globe	0.45	0.63	NO-NSR	1.00	5.00	2.52	120	Floating	24 VAC	155-306P25	
4	TU-304	TU-304 RHV	1	259-02034	N/A	0.50	2W/Sng	Globe	0.67	1.00	NO-NSR	1.50	5.00	2.25	120	Floating	24 VAC	155-306P25	
5	TU-305	TU-305 RHV	1	259-02034	N/A	0.50	2W/Sng	Globe	0.67	1.00	NO-NSR	1.50	5.00	2.25	120	Floating	24 VAC	155-306P25	
6	TU-306	TU-306 RHV	1	259-02032	N/A	0.50	2W/Sng	Globe	0.45	0.63	NO-NSR	1.00	5.00	2.52	120	Floating	24 VAC	155-306P25	
7	TU-307	TU-307 RHV	1	259-02032	N/A	0.50	2W/Sng	Globe	0.45	0.63	NO-NSR	1.00	5.00	2.52	120	Floating	24 VAC	155-306P25	
8	TU-308	TU-308 RHV	1	259-02032	N/A	0.50	2W/Sng	Globe	0.54	0.63	NO-NSR	1.20	5.00	3.63	120	Floating	24 VAC	155-306P25	

Valve Schedule

System: Air Terminal Unit Valves

Number	Unit ID	Valve Tag	Q'ty	Product Number	Line Sizes (in.)	Valve Sizes (in.)	Configuration	Body Style	Calculated Cv	Actual Cv	Failsafe	Flow (GPM)	Design P.D	Actual P.D	Close-Off (psi)	Control Signal	Voltage	Document Number	Comment
--------	---------	-----------	------	-------------------	------------------------	-------------------------	---------------	---------------	---------------	-----------	----------	---------------	---------------	---------------	--------------------	-------------------	---------	--------------------	---------

Notes:

All control valves and wells shall be installed by the mechanical contractor


Flow units are in GPM (Water) lbs/hr (Steam)

Failsafe Notation: NSR = Non-Spring Return, SR = Spring Return, FS = Failsafe

Valve Configuration Notation: 2W = 2-Way, 3W = 3-Way

Seating Notation: Sng = Single Seated, Dbl = Double Seated

Siemen Smart I Field	EMENS s Canada Limited nfrastructure I-Level Netv MCNUTT	vork De		edule NOVATION		N: new in E: existing M: existin	on Status l astallation g, to remai ng, to be m g, to be rer	n odified					BAC-IP: E BAC-M2 KNX: KN P1-1: P1 P1-2: P1 P1-3: P1 MB-RTU:	k Type Key BACnet IP FLN BACnet MS/1 BACnet MS/1 X device FLN device - FLN device - FLN device - FLN device - Modbus TCP	'P FLN devic 'P FLN devic FLN 1 FLN 2 FLN 3 device	e - FLN 1 e- FLN 2						Installation Check - Device mounted? - Power connected - Network connect - Actuator(s) wired? - Sensor(s) wired? - Flow tubes conne	? d? ted? d?	+	ressurization M : Positive press : Negative pres : Neutral press	sure ssure	(No genera	al notes)		GENE	RALNOTES				REV L 0 4/2	PATE DV 4/2025 H				REVISION H		SCRIPTION		
System						1			Ne	etwork				De	vice / Equ	ipment						Grou		Room Airflow			Supply VAV						et (1.5		Extract / Ext					Roor	n Operator	Jnit Commer	ts	
Item	Device Name	Floor	r Room No	Room / Device Description	Equipment ID	Siemens Dwg. No.	Mech Dwg No	Serrved By (Airside)	Installation Status	FLN Network No Network Type	IP Line / Loop Tag	MAC/ Device Address	No. IP Ad	idress 1	'ype E	Equipment Controlled	Coil Type	Radiation 1	Fype Rad Valve / Relay Qty	Field Power Lo Source	vice XFN bad Loa /A) (V/	MR ad (Initial)	Group Master	Comfort / Occ Precomfort / Occ Stby Precommont / Unnocc	tection / Vacant	Mode Offset	Airflow (CFM) SAV Clg S Min		W Htg SAV Min Ma	Htg SAV Ve ax Min	nt SAV Vent Max	noke Flow	Size (in)	I/D SAV W	Airflow (CFM)	el EAVO	eneral EAV) ume Hood)	et Size (in)	EAV H/D EAM	Temperature	Humidity CO2 User Interface	Lighting Pushbuttons		
1	VAVC301439	3RD	C301	1-BEDROOM APARTMENT	TU-301	400	H203	AHU-6	N 7	00439 BAC-M1		6 70643	9		DXR V	'AV (Supply)	HW	-		1	3.3 -1	-	Master	200 200 0	0		200	725	200 60	00 200	725	0 roi	und 10							x	x			
2	VAVC303B439	3RD	C303B	BEDROOM 2	TU-302	400	H203	AHU-6	N 7	00439 BAC-M1		7 70743	9		DXR V	AV (Supply)	HW	-		1.	3.3 -/		Master	150 150 0	0		150	250	150 25	50 150	250	0 roi	und 8							x	x x			
3	VAVC303A439	3RD	C303A	BEDROOM 1	TU-303	400	H203	AHU-6	N 7	00439 BAC-M1		8 70843	9		DXR V	'AV (Supply)	HW	-		1	3.3 -/	-	Master	100 100 0	0		100	175	100 17	75 100	175	0 roi	und 6							x	x x			
4	VAVC303439	3RD	C303	2-BEDROOM APARTMENT	TU-304	400	H203	AHU-6	N 7	00439 BAC-M1		1 70143	9		DXR V	AV (Supply)	HW	-		1.	3.3 -1	-	Master	225 225 0	0		225	625	225 50	00 225	625	0 roi	und 10							x	xx			
5	VAVC304439	3RD	C304	2-BEDROOM APARTMENT	TU-305	400	H203	AHU-6	N 7	00439 BAC-M1		2 70243	9		DXR V	'AV (Supply)	HW	-		1	3.3 -/		Master	225 225 0	0		225	625	225 50	00 225	625	0 roi	und 10							x	x x			
6	VAVC304A439	3RD	C304A	BEDROOM 1	TU-306	400	H203	AHU-6	N 7	BAC-M1		3 70343	9		DXR V	'AV (Supply)	HW	-		1	3.3 -1	-	Master		0				100 17			0 rot	und 6								X X			
7	VAVC304B439	3RD		BEDROOM 2	TU-307	400	H203			BAC-M1		4 70443				'AV (Supply)	HW	-			3.3 -/	-	Master	100 100 0					100 17				und 6								x x			
8	VAVC399439	3RD	C399	CORRIDOOR	TU-308	401	H203	AHU-6	N 71	00439 BAC-M1		5 70543	9		DXR V	'AV (Supply)	HW	-		1	3.3 -1		Master	200 200 0	0		200	500	200 40	00 200	500	0 ro	und 10							X	x			
9		_																			/																		_					
10		_																			/																		-					
12		_																			1																		+					
13																					1	-																	+					
14																					1																		\square					
15																					1																							
16																					/																							
17																					/																							
18																					1																							
19																					1																							
20																					1																							
21			_																		1																							
22																					/																							
23																					1																							
24																					/	-																						



OUTSIDE OF MECHANICAL ROOM. CIC TO INCLUDE PULL STRING. CIC TO RUN 1" CONDUIT FROM FUNCTION BOX TO SIEMENS PANEL. DATA CONTRACTOR TO PULL CABLE AND TERMINATE. TRANSFORMER PANELS TO BE LOCATED AS SHOWN ON ELECTRICAL DRAWINGS. MOUNTING AND FIELD WRING BY CIC, POWER WRING BY EC.


RENO N		44OP397692 0
INITIAL RELEASE LAST 04/25/25 04	EDIT DATE /25/25	R01

Control Device		Qty	Product Number		Document Number	Description
Field M	ounted Devices			-		
AUX	7	1	567-352	SIEMENS	155 272	#3 PNEU PANEL 24X24X9
PNL	7	1	PXA-ENC34	SIEMENS	149475	ENCLOSURE ASSY 34
		1	PXA-SB115V192VA	SIEMENS	588783	SERVICE BOX 115V, 24VAC, 192VA
PWR	7	1	PSH500A-LVC	FUNCTIONAL		Power Supply HILO 100VAx5 multi-tap

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240	IU - MCNUTT CENTRAL RENO
0 4/25/2025 HB SUBMITTAL SET	SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION	INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	IU PROJECT #20241429, IN ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT DATE HB HB 04/25/25 04/25/25
			SYSTEM RISER BOM

440P397692 0 **R01A**

MECHANICAL ROOM



									1				I	
BLDG	PANEL	FLN	MAC ADDR	MARK	ROOM#	ROOM DESCRIPTION	CONTROLLER	SYSTEM NAME	INSTANCE NUMBER	FLOOR	POWER SUPPLY	CIRCUIT	POWER VA	MECH DWG
439	PXCC-7 AHU-6	1	6	TU-301	C301	1-BEDROOM APARTMENT	DXR	VAVC301439	0706439	3RD	PWR-7	1	13.3	H203
439	PXCC-7 AHU-6	1	7	TU-302	C303B	BEDROOM 2	DXR	VAVC303B439	0707439	3RD	PWR-7	1	13.3	H203
439	PXCC-7 AHU-6	1	8	TU-303	C303A	BEDROOM 1	DXR	VAVC303A439	0708439	3RD	PWR-7	1	13.3	H203
439	PXCC-7 AHU-6	1	1	TU-304	C303	2-BEDROOM APARTMENT	DXR	VAVC303439	0701439	3RD	PWR-7	2	13.3	H203
439	PXCC-7 AHU-6	1	2	TU-305	C304	2-BEDROOM APARTMENT	DXR	VAVC304439	0702439	3RD	PWR-7	2	13.3	H203
439	PXCC-7 AHU-6	1	3	TU-306	C304A	BEDROOM 1	DXR	VAVC304A439	0703439	3RD	PWR-7	2	13.3	H203
439	PXCC-7 AHU-6	1	4	TU-307	C304B	BEDROOM 2	DXR	VAVC304B439	0704439	3RD	PWR-7	2	15.3	H203
439	PXCC-7 AHU-6	1	5	TU-308	C399	CORRIDOOR	DXR	VAVC399439	0705439	3RD	PWR-7	2	15.3	H203

$\begin{pmatrix} 1 \end{pmatrix}$	PXCC-7 MS/TP NETWORK
R02	SERVES: BACNET MS/TP


REVISION HISTORY 0 4/25/2025 HB SUBMITTAL SET	SIEMENS	3502 WOODVIEW TRACE SUITE 240	IU - MCNUTT CENTRAL RENO IU PROJECT #20241429, IN
	SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION	INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	ENGINEER DRAFTER CHECKED BY INITIAL RE HB HB 04/25 PNL-7 MSTP DXR NETW
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			

ITIAL RELEASE	LAST EDIT DATE
04/25/25	04/25/25
ETWOR	٢


^{440P397692} 0 **RO2**


	Control Device		Product Number		Document Number	Description
Panel	Mounted Devices					
DXR	1	1	DXR2.M11-101B	SIEMENS	A6V10502834	DXR2.M11 Room Automation Station
RS	1	1	550-975P100	SIEMENS		RS485 NETWORK END-OF-LINE TERMINATORS

REVISION HISTORY 0 4/25/2025 HB SUBMITTAL SET	SIEMENS	3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268	IU - MCNUTT CENTRAL RENO IU PROJECT #20241429, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL F HB HB 04/2
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	PNL-7 MSTP DXR NETV











AL RENO 29, IN BY INITAL RELEASE LAST EDIT DATE 04/25/25 04/25/25 RING 1	OFS6439 71 0007:0.0.23 WATER ALARM	RELAY 1	
440P397692			DRAWING NOTES: # 1. VERIFY VFD CABLE SPECIFICATIONS AND INPUT ISOLATION REQUIREMENTS WITH VFD MANUFACTURER. GENERAL NOTES: 1. ALL WRING TO MEET REQUIREMENTS OF STANDARD WIRING SPECIFICATIONS DRAWINGS. 2. 120VAC POWER BY ELECTRICAL CONTRACTOR. 3. EXACT LOCATIONS OF FIELD DEVICES TO BE COORDINATED WITH IUPUI/SIEMENS.



AL RENO 29, IN BY INITIAL RELEASE LAST EDIT DATE 04/25/25 04/25/25 RING 2		
440P397692 100B		GENERAL NOTES: 1. ALL WIRING TO MEET REQUIREMENTS OF STANDARD WIRING SPECIFICATIONS DRAWINGS. 2. 120VAC POWER BY ELECTRICAL CONTRACTOR. 3. EXACT LOCATIONS OF FIELD DEVICES TO BE COORDINATED WITH IUPUI/SIEMENS.

0	거문		<u>Щ</u>	FIELD PANEL	COMPONENT PANEL / POWER	FIELD WIF	ling	STARTER / VFD / PACKAGED CONTROLLER WIRIN
+								
7 / 27 /		PXCC-		MT6439 0007:0.0.9 4 2	WHT >>>		-1 120 deg F MENS DUCT AVERAGING	
CZ07/	ת –		PANEL			TEM	IP SENSOR	
		AHU-6		PT6439 0007:0.0.10 6	WHT		-2 120 deg F	
	_ ≂		NAME	6	BLK >>>	SIEN	MENS DUCT AVERAGING IP SENSOR AT 1K OHM	
		2		ST6439		TTE -	-3 /180DEG F	
	77 /			ST6439 0007: 0.0.11 14	WHT XX		IENS DUCT POINT	
						PLA	P SENSOR T 1K OHM	
				RT6439 [0007:0.0.12] 16 14	WHT >>>	BLK - T	-4 /180deg f 1ens duct point	
						TEM	P SENSOR T 1K OHM	
		PXCC.	FIELD	HWRT6439	WHT XX	WHT + WHT + SIEN	-5 D/240DEG F MENS LIQUID	
			D PANEL				ERSION TEMP SENSOR T 1K OHM 385	
		7AHU-		CWRT6439			6 D/240DEG F	
		0	NODE	0007:0.0.8	BLK >>>		MENS LIQUID ERSION TEMP SENSOR T 1K OHM 385	
			NAME					
			Ē	SHP6439 42 0007:0.0.1 30	WHT-~~		TE-1 10 IN WC	
				0007:0.0.1		SE BLK - SE	ETRA AIR DP SENSOR	
							OOP POWERED 4-20mA	
						(a) (b) (b)		
OIEMEN				DP16439 44 0007:0.0.2 32	WHT XX		/TE-2 /-5 IN WC	
	3						00P POWERED 4-20mA	
	ENS							
5	U 1	" "		0000 (70 46	MAIT		TE-3 /-1.0 IN WC	
				BSP6439 0007: 0.0.3	вік -××		TRA AIR DP SENSOR 541 SERIES 500 POWERED 4-20mA	
							OOP POWERED 4-20mA	
INDIANAPOLIS, IN 46268 UNITED STATES								
	SUI:							
E P A								
STA								
S, IN								
462		;						
68								
	ככ קי	=						
	IU PROJECT							
DRAFTER	ROJECT							
	#20241429							
CHECKED	ž4	ž II						

AL RENO 29, IN BY INITAL RELEASE LAST EDIT DATE 04/25/25 04/25/25 RING 3		
440P397692		<u>GENERAL NOTES:</u> 1. ALL WRING TO MEET REQUIREMENTS OF STANDARD WRING SPECIFICATIONS DRAWINGS. 2. 120VAC POWER BY ELECTRICAL CONTRACTOR. 3. EXACT LOCATIONS OF FIELD DEVICES TO BE COORDINATED WITH IUPUI/SIEMENS.



PONENT PANEL EFER TO FLOOR PLAN

PANEL GROUND LUG

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field M	ounted Device	s	•			
AE	1-3	3	GMA161.1P	SIEMENS	154004	MOD SR 24V,62LBIN,PLM
DPS	1-2	2	AFS-460-DSS	KELE INC		2-12in SWITCH W/2 SPST CONTACTS
DPTE	1	1	2641010WD11A1C	SETRA	0608cut003	EPRRIFSANEDAIB, M %) TO EPESIC
DPTE	2	1	2641005WB11A1C	SETRA	0608cut003	DP TRAN AIR,1%,+/-5" ENC
DPTE	3	1	2641001WB11A1C	SETRA	0608cut003	DP TRAN AIR,1%,+/-1" ENC
HTTE	1	1	QFM3171	SIEMENS	149991	DUCT RH & TEMP SENSOR, 4-20mA, 2%
LTDE	1	2	134–1504	SIEMENS	155 016	T'STAT, LOW TEMP,15/55,MANUAL
		6	М-648-К	KELE INC		CAPILLARY MOUNTING CLIP-INDIVIDUAL PIECE
RIB	1-2	2	RIBU1C	FUNCTIONAL DEVICES	1208cut013	RIB 120VAC 24VAC/DC SPDT
SPP	1-3	3	269-062	SIEMENS		PR269 ACCESSORY, SENSING TUBE
SPP	4	1	RPS-W	KELE		ROOM STATIC PRESSURE SENSOR-WHITE
SPP	5	1	A-306	DWYER	1011cut060	STATIC PRESSURE SENSOR OUTDOOR
TTE	1-2	2	QAM2012.750	SIEMENS	149916	DUCT AVG TEMP, PT 1K OHM(385), 24' FLEX
TTE	3	1	QAM2012.045	SIEMENS	149915	DUCT PNT TEMP, PT 1K OHM(385), 18" RIGID
TTE	4-5	2	QAE2012.005	SIEMENS	149919	IMMERSION TMP SNSR, PT 1K OHM(385) 2.5"
WD	1	1	WD-1B-C	KELE INC		WATER DETECTOR SPDT W/DEENERGIZED RELAY
Panel N	lounted Devic	es				
RE	1	1	RH2B-UL-AC24VKIT	IDEC	1202cut016	RELAY&SOC,GP DPDT AC24V W/LED
RE	2	1	RH2B-UL-AC24VKIT	IDEC	1202cut016	RELAY&SOC,GP DPDT AC24V W/LED

SUPPLY FAN START/STOP: (1) SUPPLY FANS WILL BE STARTED ACCORDIN AS SELECTED BY THE OPERATOR. MINIMUM RUN TIME SHALL BE 30 MINUT NOT MATCH THE COMMANDED VALUE, AN ALARM SHALL BE GENERATED. V FAN STARTED, THE CONTROL SEQUENCE WILL BE ENABLED.

 SUPPLY DUCT STATIC PRESSURE CONTROL:
 THE SUPPLY FAN WILL MODUL

 PRESSURE AT SETPOINT. THE INITIAL SETPOINT MAXIMUM SHALL BE 1.5" W

 DETERMINED BY THE BALANCE CONTRACTOR. SENSOR SHALL BE LOCATED

 DISCHARGE TEMPERATURE CONTROL:
 THE MIXED AIR DAMPERS, PREHEAT W

 MAINTAIN THE FOLLOWING DISCHARGE AIR TEMPERATURE SCHEDULE:

 THE MIXED AIR DAMPERS WITH MODULATE TO MAINTAIN THE MIXED AIR TEM

 THE PREHEAT VALVE WILL MODULATE TO MAINTAIN THE PREHEAT AIR TEM

 THE COOLING COIL WILL MODULAT TO MAINTAIN THE DESIRED DISCHARGE A

 OUTSIDE AIR TEMPERATURE
 DISCHARGE

0F 32F 70F

ECONOMIZER SWITCHOVER, WHEN THE OUTSIDE AIR TEMPERATURE IS BELC SHALL BE ENABLED.

BUILDING STATIC PRESSURE CONTROL: THE RELIEF DAMPER WILL MODULAT PRESSURE AT SETPOINT.

SAFETY: ALL OF THE SAFETY DEVICES ARE MANUAL RESET; THE DEVICE BEFORE RESTARTING THE AIR HANDLING UNIT. THE SUPPLY FAN WILL BE S -IF A TEMPERATURE LOW LIMIT SWITCH SENSES A TEMPERATURE BELOW 3 DISCHARGE SIDE OF THE PREHEAT COIL.

IF A FIRE ALARM SHUTDOWN CONTACT IS PROVIDED,

-IF A HIGH STATIC PRESSURE SWITCH LOCATED AFTER THE SUPPLY FAN GREATER THAN 5" W.C. (ADJ)

SHUTDOWN: WHEN THE UNIT IS SHUTDOWN BY EITHER A STOP COMMAND FOLLOWS:

SUPPLY FAN WILL BE OFF, OUTSIDE AIR DAMPER WILL CLOSE, RETURN AIR SHALL CLOSE, PREHEAT VALVE SHALL MODULATE TO MAINTAIN A PREHEA

AIR HANDLING UNIT AHU-6 SEQUENCE OF OPERATION

TCC SHALL PROVIDE AND CIC SHALL INSTALL A TEMPERATURE CONTROL PANEL TO HOUSE THE EQUIPMENT REQUIRED TO CONTROL THE AIR HANDLING UNIT. SEE MECHANICAL DRAWING FOR ADDITIONAL REQUIREMENTS.

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE	IU - MCNUTT CENTRAL RE
0 4/25/2025 HB SUBMITTAL SET		SUITE 240 INDIANAPOLIS, IN 46268	IU PROJECT #20241429, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INIT HB HB (1)
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	AHU-1 CONTROL BO
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			

TES (ADJ). IF THE SUPPLY FAN STATUS DOES WHEN THE SUPPLY FAN STATUS INDICATES THE LATE TO MAINTAIN THE DISCHARGE STATIC	
WITH A MINIMUM OF .5". BOTH SETTINGS SHALL BE 2/3 OF THE WAY DOWN THE MAIN DUCT RUN. VALVE AND COOLING VALVE SHALL MODULATE TO	
EMPERATURE SETPOINT. IPERTURE SETPOINT AIR TEMPERATURE SETPOINT. ARGE TEMPERATURE 62F 60F 55F	
OW 70 DEG F (ADJ), THE ECONOMIZER MODE	
TE TO MAINTAIN A SLIGHTLY POSITIVE BUILDING	
E THAT HAS TRIPPED MUST BE MANUALLY RESET SHUTDOWN IF ANY OF THE FOLLOWING OCCUR: 38F (ADJ). LOW LIMIT TO BE LOCATED ON THE	
SENSES A DISCHARGE PRESSURE THAT IS	
OR SYSTEM SAFETY THE UNIT WILL BE SET AS	
R DAMPER WILL OPEN, CHILLED WATER VALVE T DISCHARGE TEMPERATURE (PH—T) OF 60F (ADJ.)
NO 440P397692 0	
TIAL RELEASE LAST EDIT DATE 04/25/25 04/25/25 100 100 E	

3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	SIEMENS SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION	ILL PROJECT #20241429 IN
EAT	RUN RUN SVC SEE VAV V-1 V	INSTALLATION NOTES: 1 VAV BOX INSTALLED BY MECHAN 3 TO 5 STRAIGHT DUCT DIAMETE PROVIDE PROPER FLOW SENSING 2 DXR TO BE MOUNTED IN MANUFA (2 DXR TO BE MOUNTED FOR DXR AN 3 REFER TO BUILDING POVER TRUN 4 CLOSE DAMPER FULLY. MOUNT A PUSH ACT'R OVERRIEE BUTTON / AE-1 TO BE FACTORY MOUNTED MANUFACTURER. 5 LOCATE AS SHOWN ON FLOOR F

© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED

CHANICAL CONTRACTOR WITH AMETERS UPSTREAM OF BOX TO SING

NUFACTURER SUPPLIED CONTROLLER ENCLOSURE. R AND ALL CONTROL DEVICES.

TRUNK DRAWING FOR 24 VAC POWER

NT ACTUATOR AND SECURE TO SHAFT. TON AND ROTATE DAMPER TO FULL OPEN. INTED AND WRED BY THE VAV BOX

OR PLANS/CONTRACT DOCUMENTS

RENO	44OP397692
, IN	0
INITIAL RELEASE LAST EDIT DATE 04/25/25 04/25/25 O4/25/25	400

Contro Device	-	Qty	Product Number	Manufacturer	Document Number	Description
Field N	lounted Devices				1	
AE	1	7	GDE131.1P	SIEMENS	154 011	ACT NSR PLENUM 24/108L 5Nm
DXR	1	7	DXR2.M12P-102B	SIEMENS	A6V10502838	DXR2.M12P Room Automation Station
TTE	1	7	QMX3.P44	SIEMENS		QMX3 ROOM TEMP, RH WITH DISPLAY
TTE	2	7	QAM2030.010	SIEMENS	149915	DUCT POINT TEMP, 10K OHM TYPE 2, 4"


VAV BOX WITH REHEAT SEQUENCE OF OPERATION

DISCHARGE AIR TEMPERATURE SENSOR: TCC SHALL PROVIDE A SUPPLY AIR TEMPERATURE SENSOR FOR MONITORING PURPOSES AND TO LIMIT THE DISCHARGE AT 95F (ADJ).


OCCUPIED MODE: WHEN THE ZONE TEMPERATURE IS BETWEEN THE HEATING AND COOLING SETPOINTS, THE PRIMARY AIR DAMPER WILL BE AT THE MINIMUM CFM AND THE REHEAT VALVE SHALL BE FULLY CLOSED. ON A RISE IN ZONE TEMPERATURE ABOVE THE COOLING SETPOINT OF 72F (ADJ) PLUS THE DEAD BAND, THE PRIMARY AIR DAMPER SHALL INCREASE THE CFM AND THE REHEAT VALVE SHALL REMAIN FULLY CLOSED. ON A DROP IN TEMPERATURE BELOW THE HEATING SETPOINT OF 70F (ADJ), THE REHEAT VALVE SHALL MODULATE OPEN AFTER LOOP SIGNAL INCREASE AND THE PRIMARY AIR DAMPER SHALL MAINTAIN MINIMUM CFM UP TO THE HEATING MAX AIRFLOW. REFERENCE DIAGRAM AND SETPOINT MATRIX FOR FURTHER DETAILS.

UNOCCUPIED (NIGHT SETBACK) MODE: WHEN IN THE UNOCCUPIED MODE, THE VAV BOX SEQUENCE SHALL BE THE SAME AS THE ABOVE OCCUPIED SEQUENCE. UNOCCUPIED HEATING SETPOINT SHALL BE 65F (ADJ) AND THE COOLING SETPOINT SHALL BE 82F (ADJ). WHEN ANY TWO VAV BOXES REACH EITHER THEIR HEATING OR COOLING SETPOINT, THE AIR HANDLING UNIT SHALL START AND RUN TO MAINTAIN THE UNOCCUPIED SETPOINT. PROVIDE DIFFERENTIAL TO PREVENT SHORT CYCLING OF AHU.

0 4/25/2025 HB SUBMITTAL SET		SUITE 240 INDIANAPOLIS, IN 46268	IU PROJECT #20241429, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL HB HB 04/2
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	VAV BOX W REHEAT E







NO	44OP397692 0
ITIAL RELEASE LAST EDIT DATE 04/25/25 04/25/25	401

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field N	lounted Devices					
AE	1	1	GDE131.1P	SIEMENS	154 011	ACT NSR PLENUM 24/108L 5Nm
DXR	1	1	DXR2.M12P-102B	SIEMENS	A6V10502838	DXR2.M12P Room Automation Station
TTE	1	1	QMX3.P40	SIEMENS		QMXS ROOM TEMP, RH SENSOR ONLY
TTE	2	1	QAM2030.010	SIEMENS	149915	DUCT POINT TEMP, 10K OHM TYPE 2, 4"


VAV BOX WITH REHEAT SEQUENCE OF OPERATION

DISCHARGE AIR TEMPERATURE SENSOR: TCC SHALL PROVIDE A SUPPLY AIR TEMPERATURE SENSOR FOR MONITORING PURPOSES AND TO LIMIT THE DISCHARGE AT 95F (ADJ).


OCCUPIED MODE: WHEN THE ZONE TEMPERATURE IS BETWEEN THE HEATING AND COOLING SETPOINTS, THE PRIMARY AIR DAMPER WILL BE AT THE MINIMUM CFM AND THE REHEAT VALVE SHALL BE FULLY CLOSED. ON A RISE IN ZONE TEMPERATURE ABOVE THE COOLING SETPOINT OF 72F (ADJ) PLUS THE DEAD BAND, THE PRIMARY AIR DAMPER SHALL INCREASE THE CFM AND THE REHEAT VALVE SHALL REMAIN FULLY CLOSED. ON A DROP IN TEMPERATURE BELOW THE HEATING SETPOINT OF 70F (ADJ), THE REHEAT VALVE SHALL MODULATE OPEN AFTER LOOP SIGNAL INCREASE AND THE PRIMARY AIR DAMPER SHALL MAINTAIN MINIMUM CFM UP TO THE HEATING MAX AIRFLOW. REFERENCE DIAGRAM AND SETPOINT MATRIX FOR FURTHER DETAILS.

UNOCCUPIED (NIGHT SETBACK) MODE: WHEN IN THE UNOCCUPIED MODE, THE VAV BOX SEQUENCE SHALL BE THE SAME AS THE ABOVE OCCUPIED SEQUENCE. UNOCCUPIED HEATING SETPOINT SHALL BE 65F (ADJ) AND THE COOLING SETPOINT SHALL BE 82F (ADJ). WHEN ANY TWO VAV BOXES REACH EITHER THEIR HEATING OR COOLING SETPOINT, THE AIR HANDLING UNIT SHALL START AND RUN TO MAINTAIN THE UNOCCUPIED SETPOINT. PROVIDE DIFFERENTIAL TO PREVENT SHORT CYCLING OF AHU.

SIEMENS IN	 Dianapolis, in 46268 Nited States Hone: 317-293-8880	ENGINEER DRAFTE	R CHECKED BY INITIAL
		VAV BOX	W REHEAT







SIEMENS INDUSTRY INC.

SMART INFRASTRUCTURE DIVISION

UNITED STATES

PHONE: 317-293-8880

FAX: 317-293-0374

PXCC-7 AHU-6

© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED


IU PROJECT #20241429, IN					
ENGINEER		CHECKED BY		LAST EDIT DATE	
HB	HB		04/25/25	04/25/25	
PXCC	7 ΔH	11-6			

44OP397692 0 E100


Control Device	Qty	Product Number		Document Number	Description
Panel Mounted Devices					
PXCC 7	1	PXC36-E.A	SIEMENS	149206	PXC COMPACT 36-PT, BACNET, APOGEE
	1	LSM-FLN36.A	SIEMENS		FLN LICENSE FOR PXC36

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240		440
0 4/25/2025 HB SUBMITTAL SET	SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION	INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	IU PROJECT #20241429, IN ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT DATE HB HB 04/25/25 04/25/25 PXCC-7 AHU-6 BOM	
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED				

^{440P397692} 0 **E100A**



- DETERMINE FINAL LOCATIONS.
- 4. PROVIDE HALF MOON VENTS 4' O.C. MIN, TWO ROWS. 5. SCREEN SHALL BE MINIMUM 80% PRIVACY, KNITTED
- HDPE UV POLYETHYLENE OR PVC CONSTRUCTION 6. PLEASE CONTACT IU SIGN WHOP FOR ADDITIONAL
- CONSTRUCTION NEEDS: 812-856-0761



ARCHITECT'S PROJECT NO. 2025-03 **INDIANA UNIVERSITY - BLOOMINGTON CAMPUS BL439 MCNUTT CENTRAL RENOVATION OF EXISTING APARTMENTS** IU PROJECT NO. 20241429

MANAMANANANANANANA

SITE ACCESS NOTES

A. BUILDING ELEVATOR MAY BE USED FOR THIS PROJECT ON A LIMITED BASIS. ALL FINISHES ARE TO BE PROTECT AND EXACT TIMES COORDINATED WITH OWNER.

- B. SOUTH STAIR (C198A) MAY BE USED FOR THIS PROJECT. ALL FINISHES ARE TO BE PROTECTED FOR THE DURATION OF THE PROJECT
- INTERIOR CONSTRUCTION BARRIER AND TEMPORARY ACCESS DOORS ARE TO BE **INSTALLED PER OWNER DIV 01 REQUIREMENTS**
- D. FINAL LOCATIONS OF SITE ACCESS ELEMENTS MUST BE COORDINATED AND VERIFIED WITH OWNER BEFORE BEGINNING CONSTRUCTION
- E. DUMPSTER AND LAY-DOWN AREA MUST BE SCREENED, SEE DETAIL THIS SHEET
- CONTRACTOR IS RESPONSIBLE FOR PROTECTING PAVEMENT WITH PLYWOOD OR OTHER APPROVED MATERIAL PRIOR TO DUMPSTER INSTALLATION







APRIL 16, 2025

DRAWING INDEX

PLUMBING LEGEND

P202 2ND FLOOR PLUMBING PLAN P203 3RD FLOOR PLUMBING PLAN

P701 PLUMBING RISER DIAGRAMS

P204 ROOF PLUMBING PLAN

P901 PLUMBING DETAILS

2ND FLOOR PLUMBING DEMOLITION PLAN

3RD FLOOR PLUMBING DEMOLITION PLAN

P001

P102

P103

COVER	DRAWING INDEX, SITE PLAN	E001	ELECTRICAL LEGEND
D101	2ND & 3RD FLOOR DEMOLITION PLANS	E103	3RD FLOOR ELECTRICAL DEMOLITION PLAN
A101	3RD FLOOR PLAN	E203	3RD FLOOR LIGHTING PLAN
A111	3RD FLOOR REFLECTED CEILING PLAN	E302	3RD FLOOR POWER AND SYSTEMS PLAN
A501	SCHEDULES, DETAILS, & INTERIOR ELEVATIONS	E302A	2ND FLOOR POWER AND SYSTEMS PLAN
		E302B	2ND FLOOR POWER AND SYSTEMS PLAN
H001	MECHANICAL LEGEND		CLASSROOM C208
H102	2ND FLOOR HVAC DEMOLITION PLAN	E303	3RD FLOOR POWER AND SYSTEMS PLAN
H103	3RD FLOOR HVAC DEMOLITION PLAN	E801	ELECTRICAL SCHEDULES AND DETAILS
H104	ROOF HVAC DEMOLITION PLAN	E802	ELECTRICAL SCHEDULES AND DETAILS
H202	2ND FLOOR HVAC PLAN	E803	ELECTRICAL SCHEDULES AND DETAILS
H203	3RD FLOOR HVAC PLAN		
H204	ROOF HVAC PLAN		
H801	HVAC SCHEDULES		
H901	HVAC DETAILS		

OWNER



THE TRUSTEES OF INDIANA UNIVERSITY BLOOMINGTON, INDIANA

ARCHITECT





SPRINGPOINT ARCHITECTS PC 522 WEST 2ND STREET BLOOMINGTON, INDIANA 47403 812.318.2930 WWW.SPRINGPOINTARCHITECTS.COM

MEP ENGINEER




CMTA, INC. 9225 PRIORITY WAY WEST DRIVE, SUITE 130 INDIANAPOLIS, INDIANA 46240 317.703.6226





D9	EXISTING ELECTRICAL PANEL TO REMAIN.




2ND FLOOR POWER AND SYSTEMS PLAN

sheet title

sheet number

E302



DETAILS FOR EXACT	
	200/11010001



sheet title

sheet number

3RD FLOOR POWER AND SYSTEMS PLAN

F30