

KBSO Project #: 25142
Project Name: IU #20250569 – Replace AHU-5 and Update Controls
Issue Date: 2/12/2026

This Addendum number 1 to the drawings and specifications shall supplement, amend, and become a part of the bidding documents, plans, and specifications. All bids and construction contracts shall be based on these modifications to the original contract documents.

Part 1. General Clarification Items

- 1.01 Demolition of the existing AHU can start June 1st, 2026.
- 1.02 Owner will assist contractor for a Pre-Demolition max CFM reading of AHU in full cooling mode.
- 1.03 Contractor to provide filter media over all existing air diffusers and outlets for initial unit start up.
 - i. See owner provided drawings attached for quantity of air outlets and zones served by AHU-5.
- 1.04 Approved Haakon submittal is in the appendix at the end of the project manual.
- 1.05 The pre-purchase AHU will be shipped to the CS4 Building (1830 W. 16th St. Indianapolis, IN 46202) and the contractor will be responsible to move AHU parts from CS4 to the jobsite.

Part 2. SPECIFICATIONS

- 2.01 N/A

Part 3. DRAWINGS

- 3.01 M301 – MECHANICAL SECTIONS
 - a. Drawing reissued in its entirety.
 - b. Heat Recovery Coil condensate added to both sides of unit.
 - c. Condensate Drain piping size increased for Chilled Water Coils.
- 3.02 M901 – CONTROLS – MECHANICAL
 - a. Drawing reissued in its entirety.
 - b. Economizer mode sequence added to sequence of operation.
 - c. Low limit temp sensor relocated to be after the chilled water coil.
 - d. End Switches removed from all dampers.
 - e. Automatic Reset with Latching Relay removed for High Static and Low Static pressure sensors.
- 3.03 JCI Shop Drawing
 - a. Drawings added to set of Documents.

ATTACHMENTS:

Owner Provided Existing Ductwork Drawing

Owner Provided Existing Mechanical Zoning Drawing

M301 – MECHANICAL SECTIONS

M901 – CONTROLS – MECHANICAL

JCI Shop Drawing

Pre-Bid Walk Thru Sign-In Sheet

END OF ADDENDUM

SCIENCE
BUILDING

SECOND FLOOR F

| | |
|----------------|-----------|
| DRAWN BY: | W.S. HIE |
| CHECKED BY: | W.S. HIET |
| DATE: | 5/9/2016 |
| CAD FILE NAME: | 073-LD |
| BLDG. #: | 073 |
| CAMPUS: | IN |

M3

SHEET 3 OF 5 SHEETS



AHU #

IN073-295-AHU5-A

IN073-285-AHU6-A

A REFER TO SHEET M-000 FOR GENERAL MECHANICAL NOTES, SYMBOLS AND ABBREVIATIONS.

B REFER TO DRAWING M-500 SERIES FOR MECHANICAL DETAILS.

C REFER TO DRAWING M-600 SERIES FOR MECHANICAL SCHEDULES.

- 1 OFFSET OUTSIDE AIR DUCTWORK AS REQUIRED TO TAP INTO VERTICAL MIXED AIR DUCT.
- 2 COOLING COIL CONDENSATE DOWN THRU PENETRATION IN 2ND FLOOR MECHANICAL ROOM FLOOR. TERMINATE CONDENSATE AT FLOOR DRAIN LOCATED IN MECHANICAL ROOM ON FLOOR BELOW.
- 3 COOLING COIL CONDENSATE DOWN THRU EXISTING PENETRATION IN 2ND FLOOR MECHANICAL ROOM FLOOR. TERMINATE CONDENSATE AT FLOOR DRAIN LOCATED IN MECHANICAL ROOM ON FLOOR BELOW.
- 4 CHILLED WATER COIL CONNECTIONS.
- 5 IFB STEAM COIL CONNECTIONS.
- 6
- 7 HEAT RECOVERY COIL CONNECTIONS.
- 8 HEAT RECOVERY COIL CONDENSATE DOWN THRU EXISTING PENETRATION IN 2ND FLOOR MECHANICAL ROOM FLOOR. TERMINATE CONDENSATE AT FLOOR DRAIN LOCATED IN MECHANICAL ROOM ON FLOOR BELOW.
- 9 HEAT RECOVERY COIL CONDENSATE DOWN THRU PENETRATION IN 2ND FLOOR MECHANICAL ROOM FLOOR. TERMINATE CONDENSATE AT FLOOR DRAIN LOCATED IN MECHANICAL ROOM ON FLOOR BELOW.



REPLACE AHU-5 AND UPDATE CONTROLS
IU INDIANAPOLIS IN073 SCIENCE BLDG
CONSTRUCTION DOCUMENTS
IU #20250569
402 N Blackford St, Indianapolis, IN 46202




| | |
|---------------------|------------------|
| SCALE: | SEE SHEET |
| DRAWN BY: | ACB |
| DESIGNED BY: | ACB |
| CHECKED BY: | SO |
| DATE: | 1/22/2026 |
| PROJECT #: | 25142 |



| REVISIONS: | |
|-------------|-----------|
| # | DATE |
| ADDENDUM #1 | 2/12/2026 |

MECHANICAL
SECTIONS

M301



SETUP ALL TRENDS IN 15 MINUTE INTERVALS AND STORE FOR MINIMUM 30 DAYS.
INCLUDE TRENDS FOR THE ASSOCIATED COMMAND AND/OR SETPOINT IN ADDITION TO POINT LISTED ABOVE.
PROVIDE CHANGE OF VALUE AND INTERVAL TRENDS FOR BI AND BO POINTS.



PLAN NOTES:

- EXISTING DAMPERS DUCT MOUNTED AND EXTERNAL TO THE AHU. ACTUATORS FURNISHED AND INSTALLED BY TCC.
- HARD WIRE START/STOP SIGNAL, SPEED CONTROL AND ALARM IN THE EVENT OF LOSS OF LAN. LAN BY TCC. (TYP. OF 4 SUPPLY FANS.)
- AIRFLOW MEASURING STATION (AFMS) PIEZOMETER RINGS AND TRANSDUCER FURNISHED AND INSTALLED BY AHU MANUFACTURER. AFMS READOUT WIRED TO BAS BY C/C. (TYP. OF 4 SUPPLY FANS.)
- VFD FURNISHED, INSTALLED, WIRED, AND STARTED BY EC. (TYP. OF 4 SUPPLY FANS.)
- LOCATE 3" FROM COOLING COIL INLET. LOW TEMPERATURE SWITCHES) SHALL BE HARD-WIRE INTERLOCKED TO THE SUPPLY FAN(S) SO THAT THE SUPPLY FAN IS DE-ENERGIZED UPON SWITCH ACTIVATION.
- DUCT STATIC SENSOR TO BE HARD WIRED TO THE SAME DDC CONTROLLER WHICH CONTROLS THE AHU & FANS. CONFIRM LOCATION OF STATIC PRESSURE SENSOR WITH OWNER.
- TREND DATA AT A MINIMUM 15 MINUTE INTERVAL AND STORE DATA FOR A MINIMUM OF 30 DAYS.
- NAE PANEL EXISTING TO REMAIN.
- EBTRON GOLD OUTDOOR AIRFLOW MEASURING STATION FURNISHED BY TCC AND INSTALLED BY SMC.
- OUTDOOR AIR TEMPERATURE SENSOR EXISTING.
- BUILDING PRESSURE SENSOR LOCATED ON 2ND FLOOR TO BE REPLACED.
- CHILLED WATER PUMP STARTER / MCA BY EC.
- STEAM IFB COIL FACE & BYPASS DAMPER ACTUATORS PROVIDED BY MANUFACTURER.
- AUTOMATIC RESET WITH LATCHING RELAY AT CONTROL PANEL.

SEQUENCE OF OPERATION:

- ALL SETPOINTS TO BE ADJUSTABLE.
 - AIR HANDLING UNIT TO BE STARTED BY DDC PANEL OR FROM BUILDING AUTOMATION SYSTEM OR OPERATOR WORKSTATION. AIR HANDLING UNIT TO RUN BASED ON SCHEDULE OCCUPANCY, 24/7. FINAL SCHEDULE SHALL BE SET BY OWNER.
- AHU – AIR HANDLING UNIT
- SAFETIES AND ALARMS (NOTE ALARMS SHALL BE GENERATED AT THE BAS AND SEND NOTIFICATIONS TO STAFF AS SPECIFIED BY CLIENT):
 - THE COOLING COIL FREEZE PROTECTION PUMP WILL BE STARTED WHEN THE COOLING COIL INLET TEMPERATURE DROPS BELOW 40F (ADJ.). PUMP WILL REMAIN ENERGIZED UNTIL THE TEMPERATURE RISES ABOVE 45F (ADJ.).
 - UPON A SIGNAL FROM THE FIRE ALARM CONTROL PANEL RELAY, THE SUPPLY FAN(S) SHALL BE DE-ENERGIZED THROUGH HARDWIRE INTERLOCKS. ASSOCIATED RELIEF FAN SHALL ALSO BE DE-ENERGIZED.
 - LOW LIMIT THERMOSTAT (AT COOLING COIL INLET ONLY) SHALL DE-ENERGIZE THE SUPPLY FAN(S) THROUGH HARDWIRE INTERLOCK SHOULD ANY 1 FT LENGTH OF THE ELEMENT FALL BELOW THE THERMOSTAT SETPOINT OF 40°F (ADJ.).
 - ANNUNCIATE AN ALARM ANY TIME A LOW LIMIT THERMOSTAT IS ACTIVATED.
 - AFTER THE TEMPERATURE RISES BY 10°F (ADJ.) AND A MANUAL RESET HAS OCCURRED, A NORMAL START UP SEQUENCE SHALL BE INITIATED.
 - FULLY OPEN THE CHILLED WATER CONTROL VALVE.
 - THE PRE-HEAT COIL CONTROL VALVE SHALL MODULATE TO MAINTAIN THE PRE-HEAT TEMPERATURE SETPOINT.
 - ANNUNCIATE AN ALARM AND SHUT DOWN ON SAFETY WHEN HIGH STATIC PRESSURE LIMIT ON DISCHARGE SIDE OF SUPPLY FAN(S) EXCEEDS 3.5 IN WC (ADJ.).
 - ANNUNCIATE AN ALARM AND SHUT THE UNIT DOWN ON SAFETY WHEN LOW STATIC PRESSURE LIMIT ON SUCTION SIDE OF SUPPLY FAN(S) EXCEEDS (-)3.0 IN WC (ADJ.).
 - ANY SMOKE DETECTED BY SUPPLY OR RETURN SMOKE DETECTOR SHALL DE-ENERGIZED THE SUPPLY FANS. OA DAMPER TO REMAIN OPEN. INITIATE ALARM AT OWS.
 - ALL AHU'S SHALL INCORPORATE A FAN STARTUP DELAY FOR 3 MINUTES (ADJ.) TO REDUCE RISK OF DUCTWORK COLLAPSE FOLLOWING RESET OF A CLOSED FIRE OR SMOKE DAMPER.
 - ANNUNCIATE AN ALARM IF FAN OPERATION IS NOT CONFIRMED BY STATIC PRESSURE SENSOR WITHIN 2 MINUTES (ADJ.) AFTER COMMANDED TO RUN.
 - ANNUNCIATE AN ALARM IF A DAMPER IS CALLED TO OPEN AND NOT PROVED OPEN BY END SWITCH.
 - NORMAL OCCUPIED OPERATION:
 - FOR COLD WEATHER STARTUP ANYTIME OUTDOOR AIR TEMPERATURE IS LESS THAN 40°F (ADJ.), RUN SUPPLY FANS AT 25 HZ (ADJ.) FOR 7 MIN (ADJ.) BEFORE RAMPING FAN UP TO MAINTAIN STATIC PRESSURE. ACTIVATE SUPPLY AIR TEMPERATURE CONTROL LOOP WHILE DISABLING ECONOMIZER FOR 7 MIN (ADJ.) BEFORE BEING ENABLED. THE PREHEAT CONTROL LOOP SHALL OPERATE IN FACE AND BYPASS MODE AS SOON AS THE AHU IS CALLED TO RUN AND SET TO 65°F (ADJ.). ONCE SUPPLY FAN(S) STATUS IS PROVEN ON, THE PREHEAT SETPOINT WILL DECREASE 1°F (ADJ.) EVERY 2 MINUTES (ADJ.) UNTIL THE CONTROL SETPOINT IS REACHED.
 - FOR STARTUP ANYTIME OUTDOOR AIR TEMPERATURE IS 40°F (ADJ.) OR GREATER, SUPPLY FAN START AND RAMP UP OVER A PERIOD OF 5 MINUTES (ADJ.) TO CONTROL STATIC PRESSURE.
 - OUTDOOR AIR DAMPER TO OPEN TO MINIMUM AIRFLOW POSITION (ADJ.) AFTER STARTUP AND STATIC PRESSURE CONTROL ARE ENGAGED.
 - OUTDOOR AIR DAMPER POSITION TO MODULATE TO MAINTAIN 0.020" W.G. (ADJ.) BUILDING PRESSURE SENSOR SETPOINT. BUILDING PRESSURE SENSOR LOCATED ON 2ND FLOOR OF IU SCIENCE BUILDING.
 - THE SUPPLY AIR TEMPERATURE CONTROL LOOP SHALL OPERATE AS DESCRIBED BELOW. THE SUPPLY AIR SETPOINT SHALL BE 65°F (ADJ.). THE COOLING COIL SETPOINT SHALL BE THE SUPPLY AIR SETPOINT MINUS 2°F (ADJ.). THE PREHEAT COIL SETPOINT SHALL BE THE SUPPLY AIR SETPOINT MINUS 4°F (ADJ.). THE FINAL OFFSETS SHALL BE SET BY THE TCC TO ACCOUNT FOR FAN HEAT AND TO PREVENT SIMULTANEOUS HEATING AND COOLING.
 - HEAT RECOVERY CONTROL:
 - THE HEAT RECOVERY COIL CONTROL VALVE SHALL FULLY OPEN WHEN OAT IS <50°F (ADJ.) OR WHEN OAT IS >70°F (ADJ.). THE HEAT RECOVERY COIL CONTROL VALVE SHALL BE SHUT WHEN OAT IS WITHIN THE RANGE ABOVE.
 - STEAM FACE AND BYPASS CONTROL:
 - IF THE HEAT RECOVERY COIL DISCHARGE AIR TEMPERATURE IS EQUAL TO OR BELOW 40°F, THE IFB STEAM COIL VALVE TO BE OPEN 100% AND THE FACE AND BYPASS DAMPERS SHALL MODULATE TO MAINTAIN THE PREHEAT COIL TEMPERATURE SETPOINT.
 - IF THE HEAT RECOVERY COIL DISCHARGE AIR TEMPERATURE IS BETWEEN 40°F AND 50°F, IFB STEAM COIL VALVE TO BE OPEN 65% AND THE FACE AND BYPASS DAMPERS SHALL MODULATE TO MAINTAIN THE PREHEAT COIL TEMPERATURE SETPOINT.
 - IF THE HEAT RECOVERY COIL DISCHARGE AIR TEMPERATURE IS ABOVE 50°F, IFB STEAM COIL VALVE TO BE CLOSED 100% AND OPERATE IN FULL BYPASS.
 - COOLING CONTROL:
 - MODULATE THE COOLING VALVE TO MAINTAIN THE COOLING COIL TEMPERATURE SETPOINT.
 - SUPPLY FAN SPEED SHALL BE DETERMINED BY STATIC PRESSURE SENSOR LOCATED 90" THROUGH THE SUPPLY DUCTWORK SYSTEM IN CONJUNCTION WITH THE UNIT DISCHARGE STATIC PRESSURE. SUPPLY FAN VFDs CONTROL LOOP TO MODULATE FAN SPEED TO ACHIEVE A DUCT STATIC PRESSURE SET AT INITIALLY 1.5" W.G. (ADJ.), WHILE NOT EXCEEDING A UNIT DISCHARGE PRESSURE OF 3.0" W.G. (ADJ.). TEST AND BALANCE CONTRACTOR TO DETERMINE FINAL SETPOINT AND APPROVE WITH ENGINEER.
 - ON AHU SHUTDOWN, SUPPLY FAN STOP, OUTDOOR AIR AND RELIEF AIR DAMPERS FULLY CLOSE, AND RETURN AIR DAMPER FULLY OPENS. THE COOLING COIL CONTROL VALVE IS FULLY CLOSED, EXCEPT ON LOW LIMIT SAFETY. MODULATE THE PREHEAT COIL CONTROL VALVE TO MAINTAIN THE PREHEAT AIR SETPOINT.

- UNOCCUPIED OPERATION:
 - TRANSITIONING TO UNOCCUPIED MODE THE SUPPLY FAN AND DAMPERS SHALL OPERATE IN THE SEQUENCE DESCRIBED ABOVE.
 - TRANSITION TO OCCUPIED MODE IS BASED ON A SCHEDULE OR TERMINAL UNIT SEQUENCE.
- ECONOMIZER MODE:
 - BELOW 70°F (DRY BULB) AMBIENT (ADJ.) OUTDOOR AIR DAMPER AND RETURN AIR DAMPER TO MODULATE TO MAINTAIN 55°F (ADJ.) MIXED AIR TEMPERATURE.
 - AS THE RETURN AIR ENTHALPY RISES ABOVE THE OUTSIDE AIR ENTHALPY, THE OUTSIDE AIR DAMPER SHALL RETURN TO ITS MINIMUM POSITION.
 - SUPPLY AIR TEMPERATURE SHALL BE RESET FROM 55°F TO 60°F (ADJ.) AS OUTDOOR AIR TEMPERATURE VARIES FROM 70°F TO 30°F (ADJ.). IF RETURN AIR HUMIDITY EXCEEDS 55% RH (ADJ.), RESET THE UNIT SUPPLY TEMPERATURE TO 53°F (ADJ.) AND NOTIFY OWNER ON BAS/OWS. INCREASE SUPPLY TEMPERATURE 1°F (ADJ.) EVERY 10 MINUTES AFTER 15 MINUTES OF THIS NOTIFICATION.

IU Indy LD AHU-5

IU#20250569 JCI#6N200480

Page

0.0

0.1

1.1

1.2

1.3

1.4

1.5

1.6

1.7

1.8

1.9

1.10

1.11

1.12

V.1

V.1

Description

Title Page Drawing

Riser Communications Drawing

LD AHU-5 - Flow Layout

LD AHU-5 - BOM Drawing

LD AHU-5 - Sequence Drawing

LD AHU-5 - Panel Detail

LD AHU-5 - Point Schedule

LD AHU-5 - Point Schedule 2

LD AHU-5 - Power Wiring Details 1

LD AHU-5 - Power Wiring Details 2

LD AHU-5 - Wiring Details 1

LD AHU-5 - Wiring Details 2





















LD AHU-5 - Wiring Details 3



















LD AHU-5 - Wiring Details 4

LD AHU-5 - RAC Schedule

LD AHU-5 - Valve Schedule

LEGEND

| | | | | | |
|---|--|---|---|---|-----------------------|
|  | Main Air Supply Tube at 20 PSIG |  | Pneumatic Tube indicating Tube Number |  | Opposed Blade Damper |
|  | Dual Air Supply Tube at 15/20 PSIG Day=15, Night=20 |  | Wire Symbol indicating: number of wires and size (E.G. 2 #18 wires) |  | Parallel Blade Damper |
|  | High Pressure Air Supply Tube at 80 PSIG |  | Wire Symbol indicating: Cable Destination (DA-T), Cable number (3), Number of wires and size (E.G. 2 #18 wires) |  | Filter |
|  | Air line or Electrical Wire |  | Air Flow Measuring Station |  | Humidifier |
|  | Connected Lines or Wires |  | Electrical Wire Terminal with Appropriate Number |  | Fan |
|  | Crossing Lines or Wires, Not Connected |  | Item Located on Panel Face |  | Pump |
|  | In-Line Restrictor |  | Drawing Revision Symbol with Appropriate Number | | |

| | | | | | | | | | |
|---|--|---|--|---|--|---|--|---|--------------------------------|
|  | Heating or Cooling Coil |  | Device |  | Strap-on Bulb Type Temperature Sensing Element |  | Paddle Type Flow Switch |  | Duct Detector (Smoke, CO, CO2) |
|  | Ductwork or Piping with Flow Direction Shown |  | Bulb Type Temperature Sensing Element Located under Shield in Outside air |  | Combination Bulb Type Temperature Sensing Element and Humidity Sensor (Duct Mount) |  | Vapor Tension Temperature Sensing Element (Hi Limit) |  | 2-Way Valve with Actuator |
|  | Gage |  | Humidity Sensing Element Located under Shield in Outside air |  | Bulb Type Temperature Sensing Element |  | Vapor Tension Temperature Sensing Element (Low Limit) |  | 3-Way Valve with Actuator |
| | |  | Bulb Type Temperature Sensing Element Located inside Separable Socket/Well |  | Pressure Sensing Device |  | Current Sensing Switch or Combination Current Sensing switch & Command Relay | | |




Creating a better climate for business.


- ☐ Environmental Control System
- ☒ Facility Management System
- ☐ Air and Water System Balancing
- ☐ Fire Management System
- ☐ Security System
- ☐ Lighting Services
- ☐ Instrumentation System Installation
- ☐ Building Operations Management
- ☐ Energy Conservation Control
- ☐ Training Programs
- ☐ Performance Contracting
- ☐ Planned Service Agreements

Air Conditioning
Heating
Diagnostic Services
Coil Cleaning
Refrigeration
Automatic Temperature Controls
Facility Management Systems
Fire Management
Security Management
Building Operations and Management
Water Treatment
Electrical Equipment
Emergency Generator / Lighting Equipment
Industrial Controls / Recording / Indication Equipment

PROJECT TITLE
IU Indy LD AHU-5
IU# 20250569

| | | | |
|---|-----------------------|--|------------------|
| ARCHITECT | | ENGINEER | |
| Phone: | | Phone: | |
| MECHANICAL CONTRACTOR | | ELECTRICAL CONTRACTOR | |
| Phone: | | Phone: | |
| | | | |
| | | | |
| | | | |
| | | | |
| REFERENCE DRAWING | NO. | REVISION-LOCATION | ECN DATE BY |
|  | | Branch Information Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | |
| | | | |
| SALES ENGINEER JG | PROJECT MANAGER JB | APPLICATION ENGINEER DG | DATE 2/2/2026 |
| | | CONTRACT NUMBER 6N20-0480 | |

COMMUNICATIONS RISER






Copyright Johnson Controls, 2026.
All rights reserved.
Reuse, copying, modification or alteration of the
drawings and other information contained herein
is strictly prohibited.

| | | | | | | | | |
|--|-----------------|----------------------|-------|---|----------|------------------------------------|------|------|
| Drawing Title Riser Drawing | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | REFERENCE DRAWING | NO. | REVISION-LOCATION | | ECN | DATE | BY |
| Sales Engineer | Project Manager | Application Engineer | DRAWN | | APPROVED | | | |
| JG | JB | DG | BY | DRG | DATE | 2/3/2026 | BY | DATE |
| Project Title IU Indy LD AHU-5 IU#20250569 | | | | Branch Information Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | CONTRACT NUMBER 6N200480 | | |
| | | | | | | DRAWING NUMBER 0.1 | | |


AHU-5 – FLOW LAYOUT

LOCATED IN THE SHADE ON THE NORTH SIDE OF THE BUILDING


OA-T




Safety Shutdown Relay Coil Wiring Detail



- NEW JCI DEVICE
- NEW DEVICE BY OTHERS
- EXISTING DEVICE

| | | | | | | | | | |
|--|---|-----------------------|---|-------------------|------|-----------------|----------|------|----|
| Copyright Johnson Controls, 2026. All rights reserved. Reuse, copying, modification or alteration of the drawings and other information contained herein is strictly prohibited. | Drawing Title AHU-5 - Flow Layout | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | REFERENCE DRAWING | | NO. | REVISION-LOCATION | | | ECN | DATE | BY |
| | Sales Engineer JG | Project Manager JB | Application Engineer DG | DRAWN | | | APPROVED | | |
| | | | BY | DRG | DATE | 1/29/2026 | BY | DATE | |
| Project Title IU Indy LD AHU-5 IU#20250569 |  | | Branch Information Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | | CONTRACT NUMBER | | | |
| | | | | | | 6N200480 | | | |
| | | | | | | DRAWING NUMBER | | | |
| | | | 1.1 | | | | | | |

| BILL OF MATERIAL | | | | BILL OF MATERIAL | | | |
|------------------|------|--------------|---|------------------|------|----------------|---|
| DESIGNATION | QTY. | CODE NUMBER. | DESCRIPTION | DESIGNATION | QTY. | CODE NUMBER. | DESCRIPTION |
| CLG-O | 1 | VALVE | SEE VALVE SCHEDULE | MA-H | 1 | HT-69030NP-0 | DUCT TRANSMITTER 3%RH |
| HR-O | 1 | VALVE | SEE VALVE SCHEDULE | MA-T | 1 | TE-6328P-1 | 20', W/TE-6001-8ELEMENTHOLDER |
| PH-O | 1 | VALVE | SEE VALVE SCHEDULE | | 1 | TE-6001-8 | AVER ELEMENT HLDR QTY =10 |
| BLDG-P | 1 | DP140X25B21C | BIDIRECTIONAL + OR -0.25IN. W.C. 24 VDC / 4 TO 20 MA | OAD-O | 1 | AFB24-SR-S | BELIMO |
| | 1 | A-306-K | Outdoor Air Static | OA-T | 1 | TE-6353P-1 | OUTDOOR AIR TEMPERATURE SENSOR, 1K OHM PLATINUM, 3 IN. PROBE |
| | 1 | RPS | STAINLESS STEEL ROOM PRESSURE SENSOR WITH 1/4 INCH BARB FITTING | OA-VP | 1 | GTC116e-P+ | EBTRON TRANSMITTER W/4 INTERNAL PROBE 4 SENSORS EA. 20" PROBE LENGTH X 140 ADJACENT SIDE 10' CABLES |
| | 1 | SD-01 | SURGE DAMPENER | PH-T | 1 | TE-6328P-1 | 20', W/TE-6001-8ELEMENTHOLDER |
| CC-T | 1 | TE-6328P-1 | 20', W/TE-6001-8ELEMENTHOLDER | | 1 | TE-6001-8 | AVER ELEMENT HLDR QTY =10 |
| | 1 | TE-6001-8 | AVER ELEMENT HLDR QTY =10 | RAD-O | 1 | AFB24-SR-S | BELIMO |
| CHWE-T | 1 | TE-6300W-102 | THERMOWELL. 6 STAINLESS STEEL DIRECT MOUNT | RA-T,-H | 1 | HE-69530NP-0 | DUCT PROBE, 3%RH, PT TEMP |
| | 1 | TE-635AM-2 | WELL INSERTION TEMPERATURE SENSOR 1K OHM PLATINUM 6 IN. PROBE | SA-P | 1 | DP140005U21C | UNIDIRECTIONAL 0 TO 5IN. W.C. 24 VDC / 4 TO 20 MA |
| CHWL-T | 1 | TE-6300W-102 | THERMOWELL. 6 STAINLESS STEEL DIRECT MOUNT | | 1 | FTG18A-600R | SENSING TUBE KIT FOR P32 |
| | 1 | TE-635AM-2 | WELL INSERTION TEMPERATURE SENSOR 1K OHM PLATINUM 6 IN. PROBE | SDR-1 | 1 | RIBU1C | ENCLOSED PILOT RELAY 10 AMP SPDT WITH 10-30 VAC |
| CP-C,-S | 1 | RR20YN | POWER RELAY, 20A, SPDT, GO/NO CURRENT SWITCH | SF-C | 1 | RIBU1C | ENCLOSED PILOT RELAY 10 AMP SPDT WITH 10-30 VAC |
| DA1-P | 1 | DP140005U21C | UNIDIRECTIONAL 0 TO 5IN. W.C. 24 VDC / 4 TO 20 MA | SF-S | 1 | CSDSC-C50100L0 | CURR SW SELF CAL CLMP 0.50A-100A |
| | 1 | FTG18A-600R | SENSING TUBE KIT FOR P32 | SFPLO-A | 1 | AFS-222 | DIFFERENTIAL PRESSURE SWITCH, ADJUSTABLE, 0.05-12 IN WC |
| DAPHI-A | 1 | AFS-222 | DIFFERENTIAL PRESSURE SWITCH, ADJUSTABLE, 0.05-12 IN WC | | 1 | FTG18A-600R | SENSING TUBE KIT FOR P32 |
| | 1 | FTG18A-600R | SENSING TUBE KIT FOR P32 | | 1 | RIB24P | ENCLOSED RELAY 20 AMP DPDT WITH 24 VAC/DC COIL |
| | 1 | RIB24P | ENCLOSED RELAY 20 AMP DPDT WITH 24 VAC/DC COIL | | | | |
| DA-T,-H | 1 | HE-69530NP-0 | DUCT PROBE, 3%RH, PT TEMP | | | | |
| HR-T | 1 | TE-6001-8 | AVER ELEMENT HLDR QTY =10 | | | | |
| HR-T | 1 | TE-6328P-1 | 20', W/TE-6001-8ELEMENTHOLDER | | | | |
| HRR-T | 1 | TE-635AM-2 | WELL INSERTION TEMPERATURE SENSOR 1K OHM PLATINUM 6 IN. PROBE | | | | |
| | 1 | TE-6300W-102 | THERMOWELL. 6 STAINLESS STEEL DIRECT MOUNT | | | | |
| HRS-T | 1 | TE-635AM-2 | WELL INSERTION TEMPERATURE SENSOR 1K OHM PLATINUM 6 IN. PROBE | | | | |
| | 1 | TE-6300W-102 | THERMOWELL. 6 STAINLESS STEEL DIRECT MOUNT | | | | |
| LT-A | 2 | A70GA-1C | 15/55F, DIFF 5 FIXED,1NO/1NC MAIN OPEN LOW,1/8 X 20' BULB, | | | | |
| | 1 | TE-6001-8 | AVER ELEMENT HLDR QTY =10 | | | | |
| | 1 | RIB24P | ENCLOSED RELAY 20 AMP DPDT WITH 24 VAC/DC COIL | | | | |

| | | | | | | | | | |
|--|----------------------|---|----------------------------|--------------------------------|--|-----------------|---------------------|------|----|
| Copyright Johnson Controls, 2026. All rights reserved. Reuse, copying, modification or alteration of the drawings and other information contained herein is strictly prohibited. | Drawing Title | | | | | | | | |
| | AHU-5 - BOM | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | REFERENCE DRAWING | | NO. | REVISION-LOCATION | | | ECN | DATE | BY |
| | Sales Engineer JG | Project Manager JB | Application Engineer DG | DRAWN BY DRG DATE 1/29/2026 | | | APPROVED BY DATE | | |
| | Project Title | | Branch Information | | | CONTRACT NUMBER | | | |
| IU Indy LD AHU-5 IU#20250569 | | Johnson Controls  | | | Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | | | |
| | | | | | 6N200480 | | | | |
| | | | | | DRAWING NUMBER | | | | |
| | | | | | 1.2 | | | | |

SEQUENCE OF OPERATION

AHU CONTROLS:

All setpoints to be adjustable. Air handling unit to be started by DDC Panel, BAS, or operator workstation. AHU to run based on scheduled occupancy, initially 24/7. Final schedule shall be set by owner.

OCCUPIED MODE:

For cold weather startup anytime outdoor air temperature (OA-T) is less than 40 deg F (adj), run supply fans at 25 Hz (adj) for 7 min (adj) before ramping fan up to maintain static pressure. Activate supply air temperature control loop while disabling economizer for 7 min (adj) before being enabled. The preheat control loop shall operate in face and bypass mode as soon as the AHU is called to run and set to 65 deg F (adj). Once supply fan status (SF-S) is proven on, the preheat setpoint (PHT-SP) will decrease 1 deg F (adj) every 2 minutes (adj) until the control setpoint is reached. For startup anytime outdoor air temperature is 40 deg F (adj) or greater, supply fan start and ramp up over a period of 5 minutes (adj) to control static pressure (DA-P). Outdoor air damper (OAD-O) to open to minimum airflow position (adj) after startup and static pressure control are engaged. Outdoor air damper to modulate to maintain 0.020 in w.c. (adj) building pressure sensor setpoint (BLDG-SP). Building pressure sensor (BLDG-P) located on 2nd floor of IU Science Building. Supply fan speed (SF-O) shall be determined by a static pressure sensor (SA-P) located 90% through the supply ductwork system in conjunction with the unit discharge static pressure (DA-P). Supply fan VFDs control loop to modulate fan speed to achieve a duct static pressure set at initially 1.5 in w.c. (adj) while not exceeding a unit discharge pressure of 3.0 in w.c. (adj). Test and balance contractor to determine final setpoint and approve with engineer. On AHU shutdown, supply fan stop, outdoor air and relief air dampers fully close, and return air damper fully opens. The cooling coil control valve (CLG-O) is fully closed, except on low limit safety. Modulate the preheat coil control valve (PH-O) to maintain the preheat air setpoint.

The supply air temperature control loop shall operate as described below. The supply air setpoint (SAT-SP) shall be 55 deg F (adj). The cooling coil setpoint (CCT-SP) shall be the supply air setpoint minus 2 deg F (adj). The preheat coil setpoint (PHT-SP) shall be the supply air setpoint minus 4 deg F (adj). The final offsets shall be set by TCC to prevent simultaneous heating and cooling.

ECONOMIZER MODE:

Below 70 deg F (dry bulb) ambient (adj) outdoor air damper and return air damper will modulate to maintain 55 deg F (adj) mixed air temperature (MA-T). As the return air enthalpy rises above the outside air enthalpy, the outside air damper shall be modulated to control the mixed air temperature at the mixed air temperature setpoint (MAT-SP). Upon a drop in the return air enthalpy below the outside air enthalpy, the outside air damper shall return to its minimum position. Supply air temperature shall be reset from 55 deg F to 60 deg F (adj) as outdoor air temperature varies from 70 deg F to 30 deg F (adj). If return air humidity (RA-H) exceeds 55% RH (adj), reset the unit supply temperature to 53 deg F (adj) and notify owner on BAS/OWS. Increase supply temperature 1 deg F (adj) every 10 minutes after 15 minutes of this notification.

HEAT RECOVERY CONTROL:

The heat recovery coil control valve (HR-O) shall fully open when OA-T is less than 50 deg F (adj) or when OA-T is greater than 70 deg F (adj). The heat recovery coil control valve shall be shut when OA-T is between 50 and 70 deg F.

STEAM FACE AND BYPASS CONTROL:

If the heat recovery coil discharge air temperature (HR-T) is less than or equal to 40 deg F, the IFB steam coil valve to be open 100% and the face and bypass dampers shall modulate to maintain the preheat coil temperature setpoint. If the heat recovery coil discharge air temperature is between 40 deg F and 50 deg F, IFB steam coil valve to be open 65% and the face and bypass dampers shall modulate to maintain the preheat coil temperature setpoint. If the heat recovery coil discharge air temperature is above 50 deg F, the IFB steam coil valve to be closed and operate in full bypass.

COOLING CONTROL:

Modulate the cooling valve to maintain the cooling coil temperature setpoint.

UNOCCUPIED OPERATION:

Transitioning to unoccupied mode, the supply fan and dampers shall operate in the sequence described above. Transition to occupied mode is based on a schedule or terminal unit sequence.

SEQUENCE OF OPERATION

SAFETIES AND ALARMS:

Alarms shall be generated at the BAS and send notifications to staff as specified by client.

The cooling coil freeze protection pump (CCP-C) will be started when the cooling coil inlet temperature (CCS-T) drops below 40 deg F (adj). Pump will remain energized until the temperature rises above 45 deg F (adj).

Upon a signal from the fire alarm control panel relay (FIRE-A), the supply fan shall be de-energized through hardwire interlocks. Associated relief fan shall also be de-energized.

- Low limit thermostat (LT-A) shall de-energize the supply fan through hardwire interlock should any 1 ft length of the element fall below the thermostat setpoint of 40 deg F (adj).
- a. Annunciate an alarm any time a low limit thermostat is activated
 - b. After the temperature rises by 10 deg F (adj) and a manual reset has occurred, a normal start up sequence shall be initiated.
 - c. Fully open the chilled water control valve.
 - d. The preheat coil control valve shall modulate to maintain the preheat temperature setpoint.

Annunciate an alarm and shutdown on safety when high static pressure limit (DAPHI-A) on discharge side of supply fan exceeds 3.5 in w.c. (adj).

Annunciate an alarm and shut the unit down on safety when low static pressure limit (SFPLO-A) on suction side of supply fan exceeds -3.0 in w.c. (adj).

Any smoke detected by supply or return smoke detector (DA-SD, RA-SD) shall de-energize supply fan. OA damper to remain open. Initiate alarm at OWS.

All AHUs shall incorporate a fan startup delay for 3 minutes (adj) to reduce risk of ductwork collapse following reset of a closed fire or smoke damper.


Annunciate an alarm if fan operation is not confirmed by static pressure sensor within 2 minutes (adj) after commanded to run.

Annunciate an alarm if a damper is called to open and not proven open by end switch.

| | | | | | | | | | | | | |
|---|------------------|--|--|--|--|--|--|--|--|--|--|--|
| <p>Copyright Johnson Controls, 2026.</p> <p>All rights reserved.</p> <p>Reuse, copying, modification or alteration of the drawings and other information contained herein is strictly prohibited.</p> | Drawing Title | | | | | | | | | | | |
| | AHU-5 - Sequence | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

PANEL LAYOUT

SCALE: 1/8" = 1"




Mount Latching Relays on Sub-Panel

Body Stiffener - Do not use screws on center 2" of Sub-Panel

FACE LAYOUT

SCALE: 1/8" = 1"



Door Stiffener - Do not mount devices on center 2" of Door.


BILL OF MATERIALS

| Designation | Qty | Part Number | Description |
|-------------|-----|----------------|--|
| ENCLOSURE | 1 | PAN-ENC3042WDP | 30X42X9.25 ENCLOSURE, SOLID DOOR, PERFORATED SUB-PANEL, STEEL, UL TYPE 1 |
| CGM | 1 | M4-CGM09090-0 | ADV FIELD CONTRLLR, 18 PTS |
| XPM-4,-5 | 2 | M4-XPM09090-0 | GEN4 I/O EXP MODULE, 18 PTS |
| XPM-6 | 1 | M4-XPM04060-0 | GEN4 I/O EXP MODULE, 10 PTS |
| PS-1 | 1 | PAN-PWRSP | PWR SPLY 96 VA, 120-24 VAC w 5 A circuit breaker, Two 120 VAC outlets |
| TX-n | 2 | PAN-96VAXFR-0 | PANEL, 96VA TRANSFORMER K |
| R-1 | 1 | RH2B-ULAC24V | RH SERIES DPDT PLUG-IN GENERAL PURPOSE RELAY WITH INDICATOR - AC24V |
| | 1 | SH2B-05 | RELAY SOCKET DIN MOUNT SCREW TERMINAL USED WITH RH2B |
| R-2,3,4 | 3 | RIBL24SBM | LATCHING RELAY 20AMP WITH OVERRIDE SWITCH |
| SAFETY | 1 | RIBMNLB-6 | 2.75 TRACK MOUNT AHU FAN SAFETY ALARM AND GENERAL PURPOSE LOGIC CIRCUIT |
| TERM BLK | 10 | BAM4 | END STOP, TERM BLK |
| | 4 | DIN-3F | DIN RAIL |
| | 1 | FEM6 | END SECTION, TERM BLK |
| | 2 | M4/6 | DIN RAIL TERM BLK, 6MM GRAY |
| | 2 | M4/6.P | GROUNDING LUG GREEN/YELLOW, 6MM |
| | 2 | M4/6SNBT | 120V BLADE SWITCH |
| WIRE DUCT | 2 | T1-1530G | WIRE DUCT, 1.5" W x 3" H x 6.5FT, GRAY |

| | | | | | | |
|--|-----------------------|----------------------------|--|-------------------|------------------------------------|-----------|
| Drawing Title AHU-5 - Panel Detail | | | | | | |
| | | | | | | |
| | | | | | | |
| | REFERENCE DRAWING | | NO. | REVISION-LOCATION | | ECN |
| Sales Engineer JG | Project Manager JB | Application Engineer DG | BY | DRG | DATE | 1/30/2026 |
| Project Title IU Indy LD AHU-5 IU#20250569 | | | Branch Information BSNA - INDIANAPOLIS, IN 5920 Castleway West Dr, Indianapolis, Indiana 46250 Phone: 3176387611 | | CONTRACT NUMBER 6N200480 | |
| | | | | | DRAWING NUMBER 1.4 | |
| | | | | | | |

LD AHU-5 - POINT SCHEDULE

| Electrician/Fitter | | Point Information | | | Controller Information | | | | | | Intermediate Device | | | | Field Device | | | |
|--------------------|------------|-------------------|-------------|----------------------------------|------------------------|------------|-----------|-------------|--------------------------------|------------------------|---------------------|----------------|---------------|-----------------|------------------|---------------------|---------------------------------|------------------|
| | Point Type | System Name | Object Name | Expanded ID | Controller Details | Trunk Type | Trunk Nbr | Trunk Addr. | Cable Destination Bay/Terminal | Termination Out | Wiring /Tubing | Termination In | Device | Termination Out | Wiring /Tubing | Termination In | Device | Ref Detail Shape |
| Tag | | | | | | | | | | | | | | | | | | |
| | | LD AHU-5 | | | CGM09090 | | | | | | | | | | | | | |
| | | LD AHU-5 | | | CGM09090 | MS/TP | 1 | 4 | | | | | | | | | | |
| | UI IN-1 | LD AHU-5 | DA-T | Discharge Air Temperature | CGM09090 | MS/TP | 1 | 4 | UI IN-1 | IN1, ICOM1 | | | | | 2/22 | TEMP, TEMP | HE-6900(Duct Mnt) - TE | F160 |
| | UI IN-2 | LD AHU-5 | DA-H | Discharge Air Humidity | CGM09090 | MS/TP | 1 | 4 | UI IN-2 | IN2, ICOM2, +15V | | | | | 3/22 | OUT,GND,PWR | HE-6900(Duct Mnt) - HE | F160 |
| | UI IN-3 | LD AHU-5 | MA-T | Mixed Air Temperature | CGM09090 | MS/TP | 1 | 4 | UI IN-3 | IN3, ICOM3 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-4 | LD AHU-5 | DA-P | Discharge Air Pressure | CGM09090 | MS/TP | 1 | 4 | UI IN-4 | IN4, +15V | | | | | 2/22 | -, + | DPT2xxx (mA) | F106 |
| | UI IN-5 | LD AHU-5 | HR-T | Heat Recovery Coil Temperature | CGM09090 | MS/TP | 1 | 4 | UI IN-5 | IN5, ICOM5 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-6 | LD AHU-5 | PH-T | Preheat Coil Temperature | CGM09090 | MS/TP | 1 | 4 | UI IN-6 | IN6, ICOM6 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-7 | LD AHU-5 | CC-T | Cooling Coil Temperature | CGM09090 | MS/TP | 1 | 4 | UI IN-7 | IN7, ICOM7 | | | | | 2/22 | 2-Wire | TE | F131 |
| | BI IN-1 | LD AHU-5 | SF-S | Supply Fan Status | CGM09090 | MS/TP | 1 | 4 | BI IN-1 | IN1, ICOM1 | 2/22 | OUT, COM | Current Relay | Motor Lead | Motor Lead | See wiring detail | Motor Status (Contact) | F307 |
| | BI IN-2 | LD AHU-5 | CCP-S | Cooling Pump Status | CGM09090 | MS/TP | 1 | 4 | BI IN-2 | IN2, ICOM2 | 2/22 | OUT, COM | Current Relay | Motor Lead | Motor Lead | See wiring detail | Motor Status (Contact) | F307 |
| | BO OUT-1 | LD AHU-5 | SF-C | Supply Fan Command | CGM09090 | MS/TP | 1 | 4 | BO OUT-1 | OUT1, 24V COM | 2/22 | COIL-,COIL+ | Relay | COM, NO | 2/14 | See wiring detail | VFD (w/ Safety) (Sw Hi, EXT) | F1042 |
| | BO OUT-2 | LD AHU-5 | CCP-C | Cooling Pump Command | CGM09090 | MS/TP | 1 | 4 | BO OUT-2 | OUT2, 24V COM | 2/22 | COIL-,COIL+ | Relay | COM, NO | 2/14 | See wiring detail | Motor (Single Phase) | F1030 |
| | BO OUT-3 | LD AHU-5 | | | CGM09090 | MS/TP | 1 | 4 | BO OUT-3 | | | | | | | | | |
| | CO OUT-1 | LD AHU-5 | OAD-O | Outdoor Air Damper Output | CGM09090 | MS/TP | 1 | 4 | CO OUT-1 | OUT1, OCOM1,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | Belimo | F267 |
| | CO OUT-2 | LD AHU-5 | RAD-O | Return Air Damper Output | CGM09090 | MS/TP | 1 | 4 | CO OUT-2 | OUT2, OCOM2,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | Belimo | F267 |
| | CO OUT-3 | LD AHU-5 | SF-O | Supply Fan Output | CGM09090 | MS/TP | 1 | 4 | CO OUT-3 | OUT3, OCOM3 | | | | | 2/22 | See VFD Detail | VFD Speed Control (Vdc) | |
| | CO OUT-4 | LD AHU-5 | | | CGM09090 | MS/TP | 1 | 4 | CO OUT-4 | OUT4, OCOM4,24VAC, COM | | | | | | | | |
| | AO OUT-1 | LD AHU-5 | PH-O | Preheat Output | CGM09090 | MS/TP | 1 | 4 | AO OUT-1 | OUT1, OCOM1,24VAC ,COM | | | | | 2/22 / 2/18 | Gray, Black, Red | VA9310-HGA-2 (Vdc) (Ext Source) | F268 |
| | AO OUT-2 | LD AHU-5 | CLG-O | Cooling Output | CGM09090 | MS/TP | 1 | 4 | AO OUT-2 | OUT2, OCOM2,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | M92xx-GGx-x (Vdc) (Ext Source) | F267 |
| | | LD AHU-5 | | | XPM09090 | | | | | | | | | | | | | |
| | | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 4 | | | | | | | | | | |
| | UI IN-1 | LD AHU-5 | OA-T | Outdoor Air Temperature | XPM09090 | SA Bus | 1 | 4 | UI IN-1 | IN1, ICOM1 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-2 | LD AHU-5 | BLDG-P | Building Static Pressure | XPM09090 | SA Bus | 1 | 4 | UI IN-2 | IN2, +15V | | | | | 2/22 | -, + | DPT2xxx (mA) | F106 |
| | UI IN-3 | LD AHU-5 | CWS-T | Chilled Water Supply Temperature | XPM09090 | SA Bus | 1 | 4 | UI IN-3 | IN3, ICOM3 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-4 | LD AHU-5 | CWR-T | Chilled Water Return Temperature | XPM09090 | SA Bus | 1 | 4 | UI IN-4 | IN4, ICOM4 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-5 | LD AHU-5 | HRS-T | Heat Recovery Supply Temperature | XPM09090 | SA Bus | 1 | 4 | UI IN-5 | IN5, ICOM5 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-6 | LD AHU-5 | HRR-T | Heat Recovery Return Temperature | XPM09090 | SA Bus | 1 | 4 | UI IN-6 | IN6, ICOM6 | | | | | 2/22 | 2-Wire | TE | F131 |
| | UI IN-7 | LD AHU-5 | MA-H | Mixed Air Humidity | XPM09090 | SA Bus | 1 | 4 | UI IN-7 | IN7, ICOM7, +15V | | | | | 3/22 | OUT,GND,PWR | HE-6900(Duct Mnt) - HE | F160 |
| | BI IN-1 | LD AHU-5 | RF-S | Relief Fan Status | XPM09090 | SA Bus | 1 | 4 | BI IN-1 | IN1, ICOM1 | | | | | 2/22 | See wiring detail | Dry Contact | F301 |
| | BI IN-2 | LD AHU-5 | LT-A | Low Temperature Alarm | XPM09090 | SA Bus | 1 | 4 | BI IN-2 | IN2, ICOM2 | | | | | 2/22 / '2/22 (UI | LINE, M1, (LINE,M2) | A70 (NO) | F302 |
| | BO OUT-1 | LD AHU-5 | RF-C | Relief Fan Command | XPM09090 | SA Bus | 1 | 4 | BO OUT-1 | OUT1, 24V COM | 2/22 | COIL-,COIL+ | Relay | COM, NO | 2/14 | See wiring detail | VFD (w/ Safety) (Sw Hi, EXT) | F1042 |
| | BO OUT-2 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 4 | BO OUT-2 | | | | | | | | | |
| | BO OUT-3 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 4 | BO OUT-3 | | | | | | | | | |
| | CO OUT-1 | LD AHU-5 | BD-O | Bypass Damper Output | XPM09090 | SA Bus | 1 | 4 | CO OUT-1 | OUT1, OCOM1,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | Belimo | F267 |
| | CO OUT-2 | LD AHU-5 | FD-O | Face Damper Output | XPM09090 | SA Bus | 1 | 4 | CO OUT-2 | OUT2, OCOM2,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | Belimo | F267 |
| | CO OUT-3 | LD AHU-5 | RF-O | Relief Fan Output | XPM09090 | SA Bus | 1 | 4 | CO OUT-3 | OUT3, OCOM3 | | | | | 2/22 | See VFD Detail | VFD Speed Control (Vdc) | |
| | CO OUT-4 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 4 | CO OUT-4 | | | | | | | | | |
| | AO OUT-1 | LD AHU-5 | HR-O | Heat Recovery Coil Output | XPM09090 | SA Bus | 1 | 4 | AO OUT-1 | OUT1, OCOM1,24VAC, COM | | | | | 2/22 / 2/18 | GRY, BLK/BLK, RED | M92xx-GGx-x (Vdc) (Ext Source) | F267 |
| | AO OUT-2 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 4 | AO OUT-2 | | | | | | | | | |

| | | | | | | | | |
|---|--|---|--|--|--|------------------------------------|--|--|
| <p>Copyright Johnson Controls, 2026. All rights reserved. Reuse, copying, modification or alteration of the drawings and other information contained herein is strictly prohibited.</p> | Drawing Title | | | | | | | |
| | AHU-5 - Point Schedule 1 | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | Project Title |  | | Branch Information Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | CONTRACT NUMBER 6N200480 | | |
| | <p>Project Title</p> <p>IU Indy LD AHU-5 IU#20250569</p> | | | | | DRAWING NUMBER 1.5 | | |

LD AHU-5 - POINT SCHEDULE (CONT'D)

| Electrician/Fitter | | Point Information | | | Controller Information | | | | | | Intermediate Device | | | | Field Device | | | |
|--------------------|------------|-------------------|-------------|---|------------------------|------------|-----------|-------------|--------------------------------|------------------|---------------------|----------------------|---------------|--------------------|-----------------|-------------------|----------------------------------|------------------|
| Tag | Point Type | System Name | Object Name | Expanded ID | Controller Details | Trunk Type | Trunk Nbr | Trunk Addr. | Cable Destination Bay/Terminal | Termination Out | Wiring /Tubing | Termination In | Device | Termination Out | Wiring /Tubing | Termination In | Device | Ref Detail Shape |
| | | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | | | | | | | | | | |
| | UI IN-1 | LD AHU-5 | RA-T | Return Air Temperature | XPM09090 | SA Bus | 1 | 5 | UI IN-1 | IN1, ICOM1 | | | | | 2/22 | TEMP, TEMP | HE-6900(Duct Mnt) - TE | F160 |
| | UI IN-2 | LD AHU-5 | RA-H | Return Air Humidity | XPM09090 | SA Bus | 1 | 5 | UI IN-2 | IN2, ICOM2, +15V | | | | | 3/22 | OUT,GND,PWR | HE-6900(Duct Mnt) - HE | F160 |
| | UI IN-3 | LD AHU-5 | SF-VP | Supply Fan Velocity Pressure | XPM09090 | SA Bus | 1 | 5 | UI IN-3 | IN3, +15V | | | | | 2/22 | -, + | DPT2xxx (mA) | F106 |
| | UI IN-4 | LD AHU-5 | AFMS-OAF | Outdoor Air Flow | XPM09090 | SA Bus | 1 | 5 | UI IN-4 | IN4, +15V | | | | | 2/22 | See wiring detail | Current Input (2 Wire) | F106 |
| | UI IN-5 | LD AHU-5 | AFMS-RAF | Relief Air Flow | XPM09090 | SA Bus | 1 | 5 | UI IN-5 | IN5, +15V | | | | | 2/22 | See wiring detail | Current Input (2 Wire) | F106 |
| | UI IN-6 | LD AHU-5 | AFMS-EAF | Exhaust Air Flow | XPM09090 | SA Bus | 1 | 5 | UI IN-6 | IN6, +15V | | | | | 2/22 | See wiring detail | Current Input (2 Wire) | F106 |
| | UI IN-7 | LD AHU-5 | SA-P | Supply Air Duct Pressure | XPM09090 | SA Bus | 1 | 5 | UI IN-7 | IN7, +15V | | | | | 2/22 | -, + | DPT2xxx (mA) | F106 |
| | BI IN-1 | LD AHU-5 | SFPLO-A | Supply Air Low Pressure Alarm | XPM09090 | SA Bus | 1 | 5 | BI IN-1 | IN1, ICOM1 | 2/22 | OUT, COM | Current Relay | Motor Lead | 2/22 / '2/22 (U | See Detail | AFS-460 (NC) | F303 |
| | BI IN-2 | LD AHU-5 | DAPHI-A | Discharge Air High Pressure Alarm | XPM09090 | SA Bus | 1 | 5 | BI IN-2 | IN2, ICOM2 | | | | | 2/22 / '2/22 (U | See Detail | AFS-460 (NC) | F303 |
| | BO OUT-1 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | BO OUT-1 | | | | | | | | | |
| | BO OUT-2 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | BO OUT-2 | | | | | | | | | |
| | BO OUT-3 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | BO OUT-3 | | | | | | | | | |
| | CO OUT-1 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | CO OUT-1 | | | | | | | | | |
| | CO OUT-2 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | CO OUT-2 | | | | | | | | | |
| | CO OUT-3 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | CO OUT-3 | | | | | | | | | |
| | CO OUT-4 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | CO OUT-4 | | | | | | | | | |
| | AO OUT-1 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | AO OUT-1 | | | | | | | | | |
| | AO OUT-2 | LD AHU-5 | | | XPM09090 | SA Bus | 1 | 5 | AO OUT-2 | | | | | | | | | |
| | | LD AHU-5 | | | XPM04060 | | | | | | | | | | | | | |
| | | LD AHU-5 | | | XPM04060 | SA Bus | 1 | 6 | | | | | | | | | | |
| | UI IN-1 | LD AHU-5 | DA-SD | Discharge Air Smoke Detector | XPM04060 | SA Bus | 1 | 6 | UI IN-1 | IN1, ICOM1 | | | | | 2/22 | See wiring detail | Dry Contact | F301 |
| | UI IN-2 | LD AHU-5 | RA-SD | Return Air Smoke Detector | XPM04060 | SA Bus | 1 | 6 | UI IN-2 | IN2, ICOM2 | | | | | 2/22 | See wiring detail | Dry Contact | F301 |
| | UI IN-3 | LD AHU-5 | FIRE-A | Fire Control Panel Alarm | XPM04060 | SA Bus | 1 | 6 | UI IN-3 | IN3, ICOM3 | | | | | 2/22 | See wiring detail | Dry Contact | F301 |
| | BI IN-1 | LD AHU-5 | | | XPM04060 | SA Bus | 1 | 6 | BI IN-1 | | | | | | | | | |
| | BO OUT-1 | LD AHU-5 | LT-RESET | Low Temperature Alarm Reset | XPM04060 | SA Bus | 1 | 6 | BO OUT-1 | OUT1, 24V COM | 2/22 | COIL (Wh/Yel,Wh/Red) | RIB Relay | COM, NO (Yel, Org) | 2/14 | See wiring detail | Starter (NO) (Sw Hi, EXT Source) | F502 |
| | BO OUT-2 | LD AHU-5 | SFPLO-RESET | Supply Fan Low Pressure Alarm Reset | XPM04060 | SA Bus | 1 | 6 | BO OUT-2 | OUT2, 24V COM | 2/22 | COIL (Wh/Yel,Wh/Red) | RIB Relay | COM, NO (Yel, Org) | 2/14 | See wiring detail | Starter (NO) (Sw Hi, EXT Source) | F502 |
| | CO OUT-1 | LD AHU-5 | DAPHI-RESET | Discharge Air High Pressure Alarm Reset | XPM04060 | SA Bus | 1 | 6 | CO OUT-1 | OUT1, 24V COM | 2/22 | COIL (Wh/Yel,Wh/Rec) | RIB Relay | COM, NO (Yel, Org) | 2/14 | See wiring detail | Starter (NO) (Sw Hi, EXT Source) | F902 |
| | CO OUT-2 | LD AHU-5 | | | XPM04060 | SA Bus | 1 | 6 | CO OUT-2 | | | | | | | | | |
| | CO OUT-3 | LD AHU-5 | | | XPM04060 | SA Bus | 1 | 6 | CO OUT-3 | | | | | | | | | |
| | CO OUT-4 | LD AHU-5 | | | XPM04060 | SA Bus | 1 | 6 | CO OUT-4 | | | | | | | | | |

Copyright Johnson Controls, 2026.
All rights reserved.
Reuse, copying, modification or alteration of the
drawings and other information contained herein
is strictly prohibited.

Drawing Title

AHU-5 - Point Schedule 2

Project Title

IU Indy LD AHU-5
IU#20250569

REFERENCE DRAWING

Sales Engineer
JG

NO.

Project Manager
JB

REVISION-LOCATION

Application Engineer
DG

DRAWN

BY DRG

DATE

1/30/2026

ECN

DATE

APPROVED

BY

DATE

Branch Information

Johnson Controls
5920 Castleway Drive
Suite #130,
Indianapolis, Indiana
46250
Phone: 3176387611


CONTRACT NUMBER

6N200480

DRAWING NUMBER

1.6

WIRING DETAILS



1.7

DRAWING NUMBER

6N200480

CONTRACT NUMBER

DATE

APPROVED BY

DRAWING TITLE

AHU-5 - Power Wiring Details 1

NO.

REVISION-LOCATION

ECN

DATE

BY

FILENAME
1.7.LD AHU-5 - POWER WIRING
DETAILS 1.VSDX

REVISION DATE/TIME
02/10/26 1:57 PM

SLW

SALES ENGINEER
JG

PROJECT MANAGER
JB

APPLICATION ENGINEER
DG

DRAWN BY
DRG

DATE
2/2/2026

PROJECT NAME
IU Indy LD AHU-5
IU#20250569

Johnson Controls

BRANCH INFORMATION
Johnson Controls
5920 Castaway Drive Suite
#130,
Indianapolis, Indiana 46250
Phone: 3176387611

nn

Terminal in DDC controller.
nn indicates terminal number.

nn

Shielded cable.
Terminate & ground shield within 2
inches of entry into enclosure. Continue
shield to last device and tape back.
nn indicates cable number (labeled at
both ends of cable).

nn

Cable-no shield.
nn indicates cable number (labeled at
both ends of cable).

nnn

Indicates field-installed wiring.
nnn indicates wire number (labeled at
both ends of wire).


nnn

Indicates factory wiring.
nnn indicates wire number (labeled at
both ends of wire).




nnn

Terminal in JCI panel.
nnn indicates terminal number.

WIRING DETAILS



| | | | | | | | | | |
|---------------------------|---------------------------------|---|--|--|-----|----------------------|-----------------------|----------------------------|-----------------|
| DRAWING NUMBER 1.8 | CONTRACT NUMBER 6N200480 | DRAWING TITLE AHU-5 - Power Wiring Details 2 | | | | | | | |
| | | FILENAME 1.8 LD AHU-5 - POWER WIRING DETAILS 2.VSDX | | REVISION DATE/TIME 02/10/26 1:44 PM | SLW | SALES ENGINEER JG | PROJECT MANAGER JB | APPLICATION ENGINEER DG | DRAWN BY DRG |
| | | PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | BRANCH INFORMATION Johnson Controls 5920 Castletway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | | | | |
| | | NO. | | REVISION-LOCATION | | ECN | DATE | BY | |
| | | | | | | | | | |

Terminal in DDC controller.
nn indicates terminal number.

Shielded cable.
Terminate & ground shield within 2 inches of entry into enclosure. Continue shield to last device and tape back.
nn indicates cable number (labeled at both ends of cable).

Cable-no shield.
nn indicates cable number (labeled at both ends of cable).

Wiring Notes

— nnn —

— nnn —


nnn

Indicates field-installed wiring.
nnn indicates wire number (labeled at both ends of wire).


Indicates factory wiring.
nnn indicates wire number (labeled at both ends of wire).

Terminal in JCI panel.
nnn indicates terminal number.

WIRING DIAGRAM




SUPPLY FAN



VFD PROVIDED BY OTHERS
ACTUAL VFD TERMINATIONS TO BE FIELD DETERMINED

RELIEF FAN




VFD EXISTING
ACTUAL VFD TERMINATIONS TO BE FIELD DETERMINED

| | | | | | | | | | | | | |
|------------------------------|------------------------------------|--|--|--|--|------------------------------|-----------------------------|-----------------------------------|-----------------------------------|---------------------|------------------|------------------|
| DRAWING NUMBER 1.9 | CONTRACT NUMBER 6N200480 | DRAWING TITLE AHU-5 - Wiring Details 1 | | NO. | | REVISION-LOCATION | | ECN | DATE | BY | | |
| | | FILENAME 1.9 LD AHU-5 - WIRING DETAILS 1-VSDX | | REVISION DATE/TIME 02/10/26 1:44 PM | | SLW 0000040 | SALES ENGINEER JG | PROJECT MANAGER JB | APPLICATION ENGINEER DG | DRAWN DRG | DATE 2/2/2026 | |
| | | PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | SALES ENGINEER JG | | PROJECT MANAGER JB | | APPLICATION ENGINEER DG | | DRAWN DRG | | DATE 2/2/2026 |
| | | BRANCH INFORMATION Johnson Controls 5920 Castlaway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | | | | | | | | | |

Wiring Notes

- Terminal in DDC controller. nn indicates terminal number.
- Shielded cable. Terminate & ground shield within 2 inches of entry into enclosure. Continue shield to last device and tape back. nn indicates cable number (labeled at both ends of cable).
- Cable-no shield. nn indicates cable number (labeled at both ends of cable).
- Indicates field-installed wiring. nnn indicates wire number (labeled at both ends of wire).
- Indicates factory wiring. nnn indicates wire number (labeled at both ends of wire).
- Terminal in JCI panel. nnn indicates terminal number.

WIRING DIAGRAM



| | | | | | | | | | | | | | |
|---|------------------------------------|-----------------------------|---|------------------------------|--|-----------------------------------|------------------------------|-----------------------------|-----------------------------------|-----------------------------------|---------------------|------------------|------------------|
| DRAWING NUMBER 1.10 | CONTRACT NUMBER 6N200480 | BY DRG | DRAWING TITLE AHU-5 - Wiring Details 2 | | NO. | | REVISION-LOCATION | | ECN | DATE | BY | | |
| | | | FILENAME 1.10 LD AHU-5 - WIRING DETAILS 2.VSDX | | REVISION DATE/TIME 02/10/26 1:42 PM | | SLW 0000040 | SALES ENGINEER JG | PROJECT MANAGER JB | APPLICATION ENGINEER DG | DRAWN DRG | DATE 2/2/2026 | |
| | | | PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | SALES ENGINEER JG | | PROJECT MANAGER JB | | APPLICATION ENGINEER DG | | DRAWN DRG | | DATE 2/2/2026 |
| | | | PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | SALES ENGINEER JG | | PROJECT MANAGER JB | | APPLICATION ENGINEER DG | | DRAWN DRG | | DATE 2/2/2026 |
| PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | SALES ENGINEER JG | | PROJECT MANAGER JB | | APPLICATION ENGINEER DG | | DRAWN DRG | | DATE 2/2/2026 | | | |
| PROJECT NAME IU Indy LD AHU-5 IU#20250569 | | SALES ENGINEER JG | | PROJECT MANAGER JB | | APPLICATION ENGINEER DG | | DRAWN DRG | | DATE 2/2/2026 | | | |

Wiring Notes

Terminal in DDC controller.
nn indicates terminal number.

Shielded cable.
Terminate & ground shield within 2 inches of entry into enclosure. Continue shield to last device and tape back.
nn indicates cable number (labeled at both ends of cable).

Cable-no shield.
nn indicates cable number (labeled at both ends of cable).

Indicates field-installed wiring.
nnn indicates wire number (labeled at both ends of wire).


Indicates factory wiring.
nnn indicates wire number (labeled at both ends of wire).

Terminal in JCI panel.
nnn indicates terminal number.

Johnson Controls

5920 Castlaway Drive Suite #130,
Indianapolis, Indiana 46250
Phone: 3176387611

WIRING DIAGRAM



DRAWING NUMBER
1.11

CONTRACT NUMBER
6N200480

DRAWING TITLE
AHU-5 - Wiring Details 3

FILENAME
1.11 LD AHU-5 - WIRING DETAILS 3.VSDX

REVISION DATE/TIME
02/10/26 1:43 PM

SLW
0000040

SALES ENGINEER
JG

PROJECT MANAGER
JB

APPLICATION ENGINEER
DG

DRAWN
DRG

DATE
2/3/2026

PROJECT NAME
IU Indy LD AHU-5
IU#20250569

Johnson Controls

BRANCH INFORMATION
Johnson Controls
5920 Castlaway Drive Suite #130,
Indianapolis, Indiana 46250
Phone: 3176387611

Terminal in DDC controller.
nn indicates terminal number.

Shielded cable.
Terminate & ground shield within 2 inches of entry into enclosure. Continue shield to last device and tape back.
nn indicates cable number (labeled at both ends of cable).

Cable-no shield.
nn indicates cable number (labeled at both ends of cable).

Wiring Notes

--nnn--


nnn

Indicates field-installed wiring.
nnn indicates wire number (labeled at both ends of wire).

Indicates factory wiring.
nnn indicates wire number (labeled at both ends of wire).

Terminal in JCI panel.
nnn indicates terminal number.

WIRING DIAGRAM



DRAWING NUMBER
1.12

CONTRACT NUMBER
6N200480

APPROVED
DATE

DRAWN
DATE

DRAWING TITLE
AHU-5 - Wiring Details 4

FILENAME
1.12 LD AHU-5 - WIRING DETAILS 4.VSDX

REVISION DATE/TIME
02/10/26 1:43 PM

SLW
0000040

SALES ENGINEER
JG

PROJECT MANAGER
JB

APPLICATION ENGINEER
DG

BRANCH INFORMATION
Johnson Controls
5920 Castleway Drive Suite #130,
Indianapolis, Indiana 46250
Phone: 3176387611

nn

nn

Terminal in DDC controller.
nn indicates terminal number.

Shielded cable.

Terminate & ground shield within 2 inches of entry into enclosure. Continue shield to last device and tape back.
nn indicates cable number (labeled at both ends of cable).

Cable-no shield.

nn indicates cable number (labeled at both ends of cable).

Wiring Notes

Indicates field-installed wiring.
nnn indicates wire number (labeled at both ends of wire).

Indicates factory wiring.
nnn indicates wire number (labeled at both ends of wire).

Terminal in JCI panel.
nnn indicates terminal number.

LD AHU-5 - RAC SCHEDULE

| Space Information | | | Network / Equipment Tree Information | | | | | | Network Information (MSTP and IP) | | | | | | | | | | | | | |
|-----------------------------------|------------------------------|--------------------------------------|--------------------------------------|---------------------------------------|----------------------------------|------------------------------|---|---------------------------------|-----------------------------------|--------------------------|-------------------------------------|--------------------|----------------------------|----------------------|------------------------|-----------|-----------------|------------|-------------|-----------|---------------------|---------------------|
| Site/Building/Floor (Required) | Room Number (Optional) | Leaf Space (e.g. Room) (Required) | Device Name (Required) | Device FQR Reference (Required) | Device Description (Optional) | Equipment Name (Required) | Served By Equipment Name (Optional) | Controller Part # (Optional) | Engine Name (Required) | Trunk Name (Required) | Controller Host Name (Future) | JCI MAC Address | IP Controller Number | ZIGBEE PAN Offset | Instance # (BACoid) | N2Address | DHCP Enabled | IP Address | Subnet Mask | IP Router | ETH-1 (Optional) | ETH-2 (Optional) |
| | | | Attribute ID | | | | | | | | | | | | | | | | | | | |
| | | | Attribute Type | | | | | | | | | | | | | | | | | | | |
| IU Indy / IN073 / Floor 2 | | | LD AHU-5 | LD AHU-5 | AHU | LD AHU-5 | | M4-CGM09090-0 | NAE-8 LD | FC-1 | | 5 | | | 731105 | | | | | | | |

Copyright Johnson Controls, 2026.
All rights reserved.
Reuse, copying, modification or alteration of the
drawings and other information contained herein
is strictly prohibited.

| | | | | | | | |
|---------------------------------|----------------------|----------------------|--|---------------|-----------------|------|----|
| Drawing Title | | | | | | | |
| | AHU-5 - RAC Schedule | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| REFERENCE DRAWING | | NO. | REVISION-LOCATION | | ECN | DATE | BY |
| Sales Engineer | Project Manager | Application Engineer | DRAWN | | APPROVED | | |
| JG | JB | DG | BY DRG | DATE 2/3/2026 | BY | DATE | |
| Project Title | | | Branch Information | | CONTRACT NUMBER | | |
| IU Indy LD AHU-5 IU#20250569 | | | Johnson Controls 5920 Castleway Drive Suite #130, Indianapolis, Indiana 46250 Phone: 3176387611 | | 6N200480 | | |
| | | | DRAWING NUMBER | | R.1 | | |



IU#20250569

| | |
|--------------------------|--------------------------------------|
| Date: | 1/29/2026 |
| KBSO Project #: | 25142 |
| Project Name: | Replace AHU-5 and Update Controls |
| Project Location: | IN073 - IU Indianapolis Science Bldg |

[illegible]